SCIENTIFIC AMERICAN

[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1900, by Munn & Co.]

A WEEKLY JOURNAL OF PRACTICAL INFORMATION, ART, SCIENCE, MECHANICS, CHEMISTRY, AND MANUFACTURES.

Vol. LXXXIII.—No. 22. ESTABLISHED 1845. | NEW YORK, DECEMBER 1, 1900. | [$3.00 A YEAR. 8 CENTS A COPY.

New Coal Car Dumper.



Surface Coal Stripping.



Lake Coal-Carrying Steamer.



Electric Motor and Train—Mine Haulage.



Six-Masted Coal-Carrying Schooner.

Four-Bridge, Coal Frameway for Unloading Anthracite.

HANDLING ANTHRACITE COAL.—[See page 341.]



Scientific American.

ESTABLISHED 1845

MUNN & CO., - - - EDITORS AND PROPRIETORS.

PUBLISHED WEEKLY AT

No. 361 BROADWAY, - - NEW YORK.

TERMS TO SUBSCRIBERS

One copy, one year, for the United States, Canada, or Mexico $3.00
One copy, one year, to any foreign country, postage prepaid. £0 16s. 5d. 4.00

THE SCIENTIFIC AMERICAN PUBLICATIONS.

Scientific American (Established 1845).....$3.00 a year.
Scientific American Supplement (Established 1876) ..... 5.00 "
Scientific American Building Edition (Established 1885). ..... 2.50 "
Scientific American Export Edition (Established 1878)..... 3.00 "

The combined subscription rates and rates to foreign countries will be furnished upon application.
Remit by postal or express money order, or by bank draft or check.
MUNN & CO., 361 Broadway, corner Franklin Street, New York.

NEW YORK, SATURDAY, DECEMBER 1, 1900.

CONGESTION OF TRAFFIC AT THE GRAND CENTRAL STATION AND ITS REMEDY.

It is a remarkable fact that although New York is the second largest city in the world, it has but one railroad terminal station within its boundaries. Except in the unlikely event of the construction of a gigantic bridge across the North River, it is probable that the Grand Central Station at Forty-second Street will continue to be the only great terminal in New York. The enormous volume of traffic which it has to accommodate has for many years proved too much for the capacity of the station yard; and only by resorting to a practice which all railroad men, including the officials at the Grand Central Station themselves, condemn has it been possible to receive, make up and dispatch the large number of local and express trains which use this station. The practice referred to is that of separating the engine from its train as it enters the station, by means of what is known as a "flying switch," in which the engine is cut loose and steams swiftly ahead on to a side track, while the train runs into the station. The element of danger lies in the possibility of the switch being thrown too late, or of the train, which is not under air-brake control, being switched on to the wrong track and colliding with stationary cars. It is to the credit of the station yard management that an admittedly risky practice has been followed for many years with so few accidents.

An attempt is now being made to improve and accelerate the handling of trains in the yard by installing a complete pneumatic switch system and abolishing the flying switch; but the experience of the first three days of operation was so disastrous that a return has been made to the old plan of separating the engine from its train. Almost from the hour in which the new system was inaugurated the yard service was thrown into such disorder that trains, both suburban and express, were detained from one to two hours, either in the station or in the tunnel approach.

The fact that the flying switch is again in force proves to a demonstration that the facilities are altogether inadequate to the ever-increasing number of trains that must be accommodated; and it is evident that some radical change must be made in this terminal or the traffic within the next few years will be thrown into a condition approaching a deadlock. The simplest solution of the difficulty would be to separate the express and local trains, reserving the present station for the former, and accommodating the local trains on a series of loops built on an elevated structure above the present yard. The two outer tracks of the tunnel should be reserved for local trains. Shortly after it leaves the tunnel the incoming track should be carried on an incline to a level at which it would clear the station yard. It should then connect with a series of concentric loops, which would extend around the yard in front of the present train shed, and unite on another incline by which the outgoing local trains would leave the station. Three or four loading and unloading platforms would be provided. As part of this plan, local trains would be made up at such points as New Haven, Stamford, and New Rochelle, and would run through the New York terminal and back to these towns without change of engines. A precedent for this arrangement exists in the great loops beneath the terminal station at South Boston—the main difference being that at Boston the tracks are depressed, whereas at New York they would be elevated.

By providing such an elevated station as this, the congestion would be completely relieved and its recurrence indefinitely removed. The overcrowding of the tracks involved in making up the local trains would be avoided, as these trains would be made up at such points as Stamford and New Rochelle, and would pass through the Grand Central Station intact. There would be no insuperable structural difficulties involved in the erection of the incline and loops suggested. Moreover, it is a change which could be made with the least cost to the companies and with absolutely no discomfort or delay to the traveling public; as the terminal could be run under the present system until the very hour at which the tracks were cut and connections made between the new elevated station and the existing incoming and outgoing local tracks.

PACIFIC COAST SHIP-BUILDING.

The ship-building industry on the Pacific coast for the past three years has enjoyed a period of extraordinary activity. From January, 1898, to September, 1900, thirty-two months, the number of new ships built aggregates seventy-four, with a total tonnage capacity of 37,910. Government vessels are not included in the list. Of the new craft, forty-five, with a tonnage of 14,229, were schooners, five were barkentines of 4,597 tons, one was a barge of 632 tons, and twenty-three were steamers having a tonnage of 18,452. The largest of the schooners rated 985 tons, and of the steamers, 4,597 tons.

Of the latter, three, aggregating 7,298 tons, were built of iron, the others of wood. San Francisco builders were the constructors of the larger number of both iron and wooden ships; but almost every port on the coast, from San Pedro to Puget Sound, wherever the necessary supplies of lumber were to be had, contributed to the total result. Creditable as the exhibit is, the outlook is even more flattering. There is not a shipbuilder along the 2,000 miles of coast who has not all the work contracted for that can possibly be handled, and who could not easily duplicate his present undertakings if the supply of labor warranted it.

The cause of this prosperity is easily explained. For many years prior to 1898 the industry languished, and the carrying trade, which had been stimulated by artificial "booms," was greatly depressed. Dividends on marine property were small. The earnings were swallowed by heavy expenses. Losses by sea were not made good, and the actual number of coast ships considerably decreased.

Just at the time that the maritime prospect seemed darkest, the extraordinary development of Alaska began. It was found that the number of vessels available for this profitable traffic was far below the demand. Every vessel that could be procured was chartered for the Alaska trade. High charters caused many to be withdrawn from the coast carrying trade, and a considerable scarcity of vessels for ordinary requirements began to be felt.

It was thought that the Alaska demand would be but temporary; but the contrary proved to be the case. It continued to increase, and is bound to be permanent. The Cape Nome traffic of the present year withdrew at least a hundred vessels of all sorts from available supplies; and with new discoveries along the Alaska coast, and the location of camps that indicate every sign of permanency, the demand for a greater number of craft than was required in 1900 is undoubted. The charters for 1901 for the carrying trade of the far North already assure this. The increased demand for vessels for the Hawaiian and Philippine trade has greatly depleted the coast fleet, until there is an actual insufficiency of vessels for the ordinary coastwise traffic. The dispersion of a great number of vessels to distant points occurs at a time when the conditions of Pacific ports are more prosperous than for many years, and when trade is remarkably active. Ocean freights have continued to advance until 50 shillings is asked on wheat charters to Liverpool, yet, even at this extraordinary figure, there are but few vessels available. The values of cereals in California, Oregon and Washington are uncommonly depressed, not because foodstuffs are not in demand, but for the reason that transportation cannot be engaged to deliver them.

Except in one instance, the single tonnage capacity of the new ships is not noticeably great; but the general average indicates a gradual increase in size. The steamer "Californian," referred to, an iron ship of 4,597 tons, built for the Hawaiian trade, and now in the Philippines, is the largest vessel of her class ever launched on the Western coast. If we except the steam schooner, a vessel which is said to be of a type peculiar to Pacific Coast waters, the coast vessels do not differ greatly in character from those constructed elsewhere in the United States. The largest schooner ever built was of 600 tons. These vessels are designed for the shallow harbors of the coast, and are, consequently, all of light draught and exceptional beam. Their carrying capacity is great and their seaworthiness uncommonly good. Most of them are fitted for passenger traffic, and have cabins on the upper deck aft, though in some instances the cabins are in the center. They are fitted with compound engines, and have an average speed of ten knots. Being schooner-rigged, they are largely independent of steam propulsion. The type is economical as regards the running expenses, both of crew and motive power.

THE COMPARATIVE EFFICIENCY OF THE KRUPP, ARMSTRONG, AND SCHNEIDER-CANET GUNS.

In determining the relative efficiency of modern guns there are many elements to be taken into consideration, particularly in the case of weapons which are intended for naval service, where velocities are usually much higher than those common in weapons for field service. A comparison of relative efficiency must take note of all ballistic features. As a matter of fact, the methods of designation used are apt to be misleading, for the reason that they make too much of certain elements of efficiency, and too little of others. Thus, we find that, popularly speaking, it has become the fashion to quote the muzzle velocity of a gun in preference to any other of its ballistic capabilities. If the public hears that a gun of a certain caliber is capable of a muzzle velocity of 3.000 feet per second, as against velocities of 2,600 or 2,800 feet per second in other guns of the same caliber, it is apt to consider that the high velocity weapon is incontestably the most effective. This superiority, however, by no means follows; for the mere statement of the muzzle velocity, unaccompanied by any statement of the weight of the shell to which such velocity is imparted, conveys no information as to the actual hitting power of the gun. Then again the relative efficiency may further be modified by a statement of the weight of the gun itself, for it is evident again that if two guns, one of which is considerably lighter than the other, show the same muzzle energy, the lighter gun is ton for ton a much more effective weapon. A further modification is introduced when the question of the "remaining velocity and energy" is introduced; for although a light projectile, issuing from the muzzle of a gun at an extremely high velocity, may have the same muzzle energy as a heavier projectile with a lower muzzle velocity, the lighter projectile will lose its velocity far more rapidly as the range is covered, and what is known as the "remaining velocity and energy" of the heavier shell will be relatively greater, the greater the distance that is covered. It is mainly for this reason that many of our naval officers regret to see the 13-inch guns displaced by the 12-inch, the hitting power of the 13-inch shell at long ranges being considerably greater than that of the lighter 12-inch shell.

In determining upon the armament of their navy, the Germans have evidently been governed by this consideration; for it is a fact that the Krupp guns, with which their ships are armed, fire projectiles which are considerably heavier for any given size of gun than those used in any other navy. Although the muzzle velocities given in the ballistic tables of these guns are not so high as those of other nations, the muzzle energies are greater and the "remaining energies" are in some cases enormously so. Just how great is this difference is shown in an article which we publish in the current issue of the SUPPLEMENT, which contains a series of graphical comparisons of the relative ballistic energies of the Krupp guns and those of the great firms of Armstrong and Schneider-Canet.

Thus, in comparing the velocities and energies of the Krupp 9½-inch gun with the Armstrong weapon of the same caliber, we find that, although the muzzle velocity of the Armstrong projectile is 762 meters per second, as against 729 meters per second for the Krupp gun, at 1,750 meters from the muzzle the velocities are equal, and at 5,000 meters the Krupp has a remaining velocity of 491 meters, as against a remaining velocity for the Armstrong shell of only 448 meters per second. The loss of velocity is due to the fact that the Armstrong projectile, weighing only 159·7 kilogrammes, as against 218 kilogrammes for the Krupp projectile, is more influenced by the resistance of the air, and therefore loses its velocity more quickly. Although the velocity of the Armstrong weapon is 33 meters greater than that of the Krupp gun, its muzzle energy is 1,098 meter-tons smaller, and at a range of 5,000 meters its energy is still 1,012 meter-tons less. Judging the two guns on the basis of the amount of energy developed per kilogramme of weight of gun, we find that at the muzzle it is for the Armstrong 176·8 meter-kilogrammes per kilogramme of weight of gun, and that in the Krupp weapon it is 214·4 meter-kilogrammes per kilogramme of the weight of the gun.

Comparing the guns on the basis of their armor-piercing ability, it is shown that while the Krupp 9½-inch rapid-fire gun can perforate 30 centimeters of Harveyized armor up to 3,100 meters range, an Armstrong gun of the same caliber, in spite of its greater velocity, can do this only up to 1,250 meters. Harveyized armor 25 centimeters thick is perforated by the Krupp gun up to 4,500 meters, by the Armstrong gun only up to 2,400 meters, while the Schneider-Canet 9½ inch gun cannot perforate that thickness at a range of over 2 000 meters.

Although a strong case is made out for the superiority of the Krupp guns along the lines referred to, there is one drawback to the use of the heavier projectiles which must not be lost sight of. We refer to the fact that the greater weight of the shell will reduce the total number of rounds that can be carried for each gun; a consideration which is of importance where every ton of the displacement of a ship is valuable when it comes to the question of distribution among the contending claims of armor, engines, stores, and ammunition. Furthermore, the increased weight must tell somewhat against the rapidity of handling; and if the ammunition is to be handled at the same speed, it becomes necessary to install heavier machinery for operating the hoists.

THE HEAVENS IN DECEMBER.

BY HENRY NORRIS RUSSELL, PH.D.

The close of the nineteenth century is marked by no celestial pageant. Indeed, the heavens are more than usually bare, for all the outer planets, except Neptune, are hidden behind the sun, and the inner ones are all three morning stars. So on the last evening of the century we shall see those silent and eternal stars alone which present the same aspect to us that they did to the sages of the East more than thirty centuries ago—Orion and the Pleiades, familiar to star-gazers when the Book of Job was yet unwritten, even as in present times, and seeming even more inconceivably far beyond our reach to us than to them.

To the fixed stars, therefore, must our attention be chiefly directed, when, as our custom is, we survey the evening skies. At 9 P. M. on December 15, the Milky Way extends in a broad span across the sky from east to west, passing a little north of the zenith. It is much brighter in the west than in the east, and also much more irregular in form and brilliancy.

Following its line from west to east, and noting the principal constellations, we come at first to Cygnus, a great cross of stars standing erect right along the center of the Galaxy, and close above the western horizon. Some distance higher up, and nearly overhead, is Cassiopeia, marked by a zigzag line of bright stars; and the next group to the east is Perseus. Midway between the last-named constellations is a bright spot in the Milky Way, which, with even the smallest telescope, is seen to be a magnificent cluster of telescopic stars.

Still following the Milky Way down toward the east, we next reach Auriga, whose brightest star, Capella, considerably surpasses any that we have so far passed. Below is Gemini, containing the conspicuous pair Castor and Pollux, both of which are almost of the first magnitude. Their line continued downward points out a little hazy spot of light which is the cluster Praesepe, in Cancer, the most characteristic feature of the constellation. The separate stars of this cluster cannot be separated by the naked eye, but are clearly seen with a fieldglass.

To the right of Cancer is Canis Minor, whose only conspicuous star is the brilliant Procyon. Further on in the same direction is Sirius, which, even at its present low altitude, is beyond comparison the brightest star in sight. The lower part of Canis Major—to which constellation it belongs—has not yet risen.

Above Sirius is Orion, which is too familiar to need description here, and high above him again is Taurus. Aldebaran, Sirius, and the two brightest in Orion, Rigel and Betelgeuse, form a remarkably perfect parallelogram.

Below and to the right of Orion is the little constellation Lepus, the Hare, which between the hunter Orion and his Great and Little Dogs must be pretty hard pressed. Just above Rigel is a moderately bright star, which is Beta Ericlani; and the classic river is represented by a long stream of faint stars extending thence to the westward, and then southward and eastward to the horizon, and filling up most of the southeastern sky.

The almost equally irregular and extensive shape of Cetus and Pisces similarly occupy the southwest. Above is Aries, a little south of the zenith, below which to the west is Andromeda, with the great square of Pegasus further down and standing on one corner.

In the northern heavens we may note that the Little Dipper hangs directly down from the Pole Star and that Draco lies below it. The Great Dipper is on the right, the last star of its handle out of sight near the horizon, and the head and paws of the Great Bear extend from it toward Gemini and Cancer.

THE PLANETS.

This month has more than the usual number of planetary conjunctions with the sun; but these are unfortunately not observable phenomena.

Mercury is morning star in Libra and Scorpio all the month. His greatest elongation occurs on the 7th, and throughout the first half of December he is well placed for observation, rising about two hours before the sun. On the morning of the 22d he passes close to Uranus, and on that of the 30th close to Jupiter, but in both cases the planets are too much involved in the dawn to be easily seen.

Venus is morning star in Virgo, Libra and Scorpio, rising nearly three hours before the sun on the 1st, and more than two hours on the 31st. She is receding from the earth and growing fainter, but remains as always the brightest of the planets.

Mars is rapidly approaching opposition and becoming more conspicuous. He is in Leo, moving slowly eastward and growing brighter. By the end of the month he will be a brilliant object, brighter than a first magnitude star, and rising about 10 P. M.

Jupiter, Saturn and Uranus are all in conjunction with the sun during this month; Uranus on the 4th, Jupiter on the 13th, and Saturn on the 28th, and all are invisible during the month, unless perhaps Saturn might be seen in very clear air just after sunset in its very first days.

Neptune is almost opposite to the three planets last named, and comes to opposition on the 19th. He is situated on the boundary of Taurus and Gemini, and is invisible to the naked eye, and, indeed, hardly worth looking at in any but large telescopes.

THE MOON.

Full moon occurs on the morning of the 6th; last quarter on the afternoon of the 13th; new moon on that of the 21st; and first quarter on the evening of the 28th. The moon is nearest the earth on the 3d, most remote on the 15th and nearest again on the 30th. She passes Neptune on the morning of the 7th, Mars on the evening of the 12th, Venus on the night of the 18th, Mercury on the morning of the 20th, Uranus at noon the same day, Jupiter on the morning of the 21st, and Saturn on that of the 22d.

At 1 A. M. on the morning of the 22d the sun enters the sign of Capricorn, and, according to the almanacs, "winter begins." And with the stroke of midnight on the 31st the nineteenth century closes.

Oyster Bay, N. Y., November 19, 1900.

COHERERS.*

BY AUG. RIGHI, PROFESSOR AT THE UNIVERSITY OF BOLOGNA.

The phenomena utilized in coherers has been discovered by successive stages. Varley, in working with a system of lightning arrester for telegraph circuits, found that a conducting powder unmixed with insulating powder could not be used, as after the discharge had traversed it the particles were arranged so as to form a conducting mass. But it was supposed that the heat of the discharge produced the phenomenon. A diminution of resistance produced by weak currents was not really discovered until 1884 by Prof. Calzecchi-Onesti. He used in his experiments metallic filings contained in an insulating tube with two electrodes and observed that when the tube was slightly turned about its axis the conductibility acquired by the filings disappeared. M. Branly observed later a similar phenomenon and found that the action might be obtained by allowing a spark to pass in the neighborhood of the tube and that the original resistance was restored by a shock. Prof. Lodge arrived at the same results in 1889 by studying a fact observed already by Prof. Hughes, but unknown to him, that a very small spark between two conductors which were almost touching established a communication which disappeared by a shock.

It is not yet known exactly in what manner the phenomena of the coherer are accomplished. According to M. Branly, it is due to a modification of the dielectric between the particles, and according to Mr. Lodge it is due to exceedingly small sparks between them which give place to the production of contacts. This explanation may be completed by admitting also the possibility of slight movements of the particles by the electric forces which would arrange them in conducting filaments. According to the first theory, the shocks would have the effect of renewing the portions of the dielectric between the particles, and according to the second the shocks break the adherence produced by the sparks. The late researches have given useful data without deciding the question of the cause of the phenomena. Thus the microscopic observation made by Messrs. Arons and Van Gulick, those of M. Vincentini and Di Ciommo and Campanile upon coherers with mercury drops and those of Melagoli by the photographic method seem to uphold Mr. Lodge's views, for they have permitted observing small movements of the particles and small sparks at the instant an electric wave was produced at some distance. M. Tommasina has obtained curious chains formed by adherent metallic particles, and M. Sundorph has succeeded in removing most of the iron filings forming a coherer without causing a disappearance of the conductibility produced by a wave. Besides, the adherence produced by a small spark between two conductors which touched slightly has been observed by Mr. Lodge and lately by Mr. Maclean (United States). But on the other hand, certain facts seem difficult to explain by the theory of Mr. Lodge. For instance, peroxide of lead acts in a contrary manner to metal filings, for its conductivity diminishes under the action of electric waves and it is the same for other substances, as, according to Mr. Rose, magnesium and potassium in kerosene. To these facts, contrary to Mr. Lodge's theory, it must be added that Mr. Branly made coherers in which the particles were fixed in a solid dielectric mass. In any case, it seems that the presence of a thin layer, of oxide, the most often, at the surface of the particles is necessary or at least useful for the working of coherers. It is true that they have been made with gold or platinum filings or carbon powder, but the influence of the surface layer has been well demonstrated by M. Blondel, who produced a film of sulphide of silver in increasing thickness at the surface of silver particles and found that a certain thickness of layer exists which gives the maximum effect.

Certain coherers lose their conductibility spontaneously, as Messrs. Branly, Ducretet, Popoff, Tommasina, and others have shown. Coherers of this kind would simplify experiments greatly, as a shock to the tube would not be necessary. In general, the automatic striker of M. Popoff is used, in which a relay is worked which operates a secondary circuit including the striking magnet. According to the carbon coherers recently described by Tommasina, this will not be necessary, and a simple telephone, which may contain the coherer in the interior, will reveal the waves. The form and constitution of coherers has been greatly varied by Bowlker, Maclean and others, and the arrangements of M. Tissot and Jervis Smith are especially remarkable. The frequent use of filing tubes in the last year has furnished us with data for some practical rules for the best construction. In general, it may be said that the sensitiveness is greater as the space filled by the filings is smaller and its particles smaller. But at the same time it is sensitive to outside influences, and its working is less sure. The choice of the metal is important, and it appears that nickel is the most advantageous. Again, it is well to completely inclose the glass tube and to make a vacuum in it, to be sure that the sensitiveness does not vary in time, on account of a surface alteration produced by contact with air. But few measurements have been made upon these phenomena up to the present, but it is known that the lowering of resistance produced by the discharge of a condenser through the filings is a function not only of the charge, but also of its potential, and that for a given capacity there is no effect when the potential is below a certain critical value.

*Lecture delivered at the Congress of Physics. Reported by special Paris correspondent of the SCIENTIFIC AMERICAN.

SCIENCE NOTES.

The Duke of Abruzzi has chartered the Gothenburg whaler "Capella" to proceed to Franz Josef Land in search of three missing Arctic exploration expeditions.

The supply of clams on the New England coast is diminishing. Extensive areas which four or five years ago produced great numbers of clams are now practically barren. The demand has increased at such a rate that too large a number of seed clams have been removed, and extinction quickly follows and the beds do not recover themselves.

Experiments in forestry are being carried on in California, the idea being to determine as near as possible the value of timber to a watershed. The rainfall in the lands which have been set apart for the experiments is accurately measured, and the relative amount of run-off is carefully estimated. The experiments are being conducted on a very extensive scale, so they will undoubtedly prove of great value.

The Department of Agriculture is preparing an order on the recommendation of the Department of War setting aside as forest reserves the island of Panay and the island of Pauitaui; the latter is one of the Jolo Islands. It is found that these are the richest islands in the world for rubber trees. It is the desire of the authorities in Washington to have the trees preserved, in view of the fact that our rubber supply may become exhausted.

A Chinese banknote, issued during the Ming Dynasty, about A.D. 1390, has been placed in the British Museum, among the specimens of early printing from China. The surface of the note is black with age, though the characters upon the face of it are quite discernible. This is supposed to be the earliest specimen extant of a bank note issued from any country, and is about 300 years anterior to the issue of the first note in Europe, from Stockholm.

The London Lancet complains that the ordinary closed cab is a distinct menace to health. It says they are the undoubted source of infection; microbes infesting the cushions and the mats on the floor, and the air might easily contain pathogenic organisms left by a previous user. Hansom cabs are considered to be decidedly more sanitary, but they are considered as a kind of death trap in wet weather, when those riding in them are completely inclosed by windows and aprons, making it impossible to release themselves in an emergency.

The long looked for trial of the third-rail system on the New York elevated roads was recently carried out on the Second Avenue branch, when six trips were made between 54th Street and 92d Street. The trial train consisted of six cars, the two end cars being each equipped with four motors. The two motor cars were arranged so that the cabs were respectively at the front and rear ends of the train. The trip from 92d Street to 54th Street, a distance of thirty-eight blocks, was run in four minutes, at a speed of thirty miles an hour. The superiority of the motors over the old steam locomotives was shown in the rapid acceleration; and the substitution of the air-brake for the old vacuum brake was noticeable in the greater rapidity with which the stops were made. Judging from the results achieved on the trials, it is expected that the trains will run from the Battery to 155th Street on the Sixth Avenue line in forty minutes, instead of forty-nine minutes, which was the time taken under the old system. The new and the old cars are similar in appearance, the former being somewhat wider. In place of the old steam heating and oil lighting, they will, of course, be lighted and heated by electricity.

ARTIFICIAL LIGHTNING.

The electrically illuminated sign herewith shown is the work of Mr. P. M. Lincoln, chief engineer of the Niagara Falls Power Company, to whom we are indebted for our illustration and particulars. The sign may truthfully be called a miniature artificial thunder storm, the term "artificial" being used advisedly for the reason that the storm is strictly artificial and in no sense a mere imitation. The flashes of lightning and the thunder claps of a midsummer storm are repeated in the flashing illumination and the accompanying succession of sharp reports of this really magnificent electrical display. The sign consists of a large glass condenser charged with alternating currents of high potential. The partial and complete discharges of the condenser are the cause of the electrical display around the letters and over the surface of the glass. At low potentials each letter is surrounded by a beautiful violet fringe of brush discharge. As the potential is raised streamers begin to shoot out from the sharp corners of the letters and extend at first for a distance of about one inch over the plate. The length of these streamers increases with the rising voltage, until they form a brilliant and shifting halo, reaching out for a distance of 12 inches or more from the letters. Up to this point the electric discharges are only partial, but upon raising the voltage still higher, complete discharges occur, each being accompanied by a loud report. The white crooked lines of the illustration show some of the paths of these complete discharges. When the voltage is sufficiently high, each illumination is accompanied by one of these complete discharges, and when the frequency of 125 periods per second is reached, the discharge is extraordinarily brilliant, and the accompanying reports are strongly suggestive of a regiment of soldiers at rifle practice. Although the device is somewhat expensive, its effect when used as an advertising device is remarkably successful.



ARTIFICIAL LIGHTNING.

FIGHTING FIRE WITH WINE.

BY CHARLES FREDERICK HOLDER.

California has for four or five years been visited by a short rain supply, which has caused no little annoyance, trouble and expense to almost every industry in the southern part of the State, though certain regions have had their normal rainfall. In some localities water has almost entirely given out, and small ranchers have deserted their places and driven their stock to more favored sections. One of the most serious results of the lack of rain has been the forest fires, which in the past few years have raged with unprecedented violence and devastated hundreds of square miles of forest, which will not reproduce themselves in a century.

In many parts of California these fires have occurred owing to the dry conditions which have prevailed. Perhaps the most remarkable fire occurred near the town of Wrights, in the Santa Cruz Mountains, south of San Francisco. Here the fire was started, as in many other instances, by an irresponsible rancher who was burning brush. The wind sprang up suddenly, swept the flames into the forest, and in a very short time a fierce wall of flame was rushing up the west slopes of the Coast Range, carrying destruction before it. The mountains here were covered with a fine growth of old oaks, mazanits and madrones—landmarks in the country—which fell like straw before the destroyer. The wall of flame swept to the summit and descended into the cañons, following these rivers of verdure in and out, rushing on in an ever-increasing volume.

In the pathway of the fire was the ranch and Mare Vista winery of E. E. Meyer, one of the largest wine-making establishments and vineyards in Santa Clara County. To protect it and the homes in the vicinity, the people of the surrounding country assembled en masse, organized themselves into an efficient body of fire fighters and began a campaign in which striking acts of valor were performed. It was impossible to stay the flames, and as they went rushing down the cañon toward the winery, destruction of the valuable property seemed inevitable, and the result demonstrated the necessity of having in this and other States men who will make a study of fighting fire as a science. Trees in advance were cut down; ditches of earth dug, and every expedient known to fire fighting of today was tried; but so fierce were the flames that they seemed to leap hundreds of feet into the air, bounding in lurid sheets over the breaks, and in an incredible short time swept down to the winery, as shown in the accompanying illustration, and surrounded it. Under ordinary circumstances it would have seemed impossible to save the building, but the band of workers rallied under the intelligent lead of the Meyers, and men were posted on the roof who poured streams of water upon every portion. Young Mr. Meyer was held by ropes from a window while he used the hose upon the flames which were licking up the timbers at the base of the building, the heat being so intense that a stream had to be played upon his body.

LARGE WINE VATS WHICH WERE USED TO SUPPLY THE FIRE PUMP.

A FIRE EXTINGUISHED BY THE USE OF WINE.

It was believed that the winery could be saved, when, without warning, the water gave out. Some large trees, which were dropping in every direction, had fallen upon the supply pipes, crushing them in and clogging the reservoir. This was an unexpected catastrophe, but the resources of the fire fighters were by no means exhausted, though a desperate expedient was resorted to. The owner of the winery gave the order to attach the hose to the great vats of Zinfandel wine which were stored in the cellar (see illustration), and man the wine pumps. This was promptly done, and an exact picture of the situation at this time is here shown. Wine had been used in this way before, but the owner was not aware, in all probability, of the precedent. In a few moments valuable wine was being pumped upon the flames with remarkable effect. In the words of a witness, "it acted like some chemical prepared for the purpose." Wherever it struck, the flame was smothered at once, peculiar clouds of smoke rising, telling that the chemical combination was a success; so successful, indeed, so apparent, that the exhausted men, who had been working for hours, and whose clothing and hair were charred, raised a cheer and began the fight with renewed vigor. In a letter to the writer, Mr. Meyer says: "My cellar is surrounded by large pine trees, and these were burning furiously, throwing the flames toward the building which caught fire in several places. The wine I found to be a far better extinguisher than water. The wine I used was young, hardly through fermentation. It contained about one per cent of sugar, and was still quite warm. I had two pumps going, each throwing a one-inch stream."

Four thousand gallons of this wine was thrown upon the flames in this way before the building was safe, probably one of the most remarkable and successful methods of fighting fire known. The method was somewhat expensive, as the wine retailed at 50 cents per quart when bottled, and $8,000 in wine was used, yet it saved buildings and machinery worth many thousand dollars and demonstrated that a winery has a protective against fire in its vats if the owner has the courage and temerity to use it.

Photographic Telegraph Receivers.

Messrs. Siemens & Co., of London, have patented an invention regarding telegraph receivers of the photographic description. In this invention the photographic impression is produced by the deflection of the cathode rays relatively to the recording surface through the agency of the electromagnetic effect of the signaling current. The cathode rays act directly through the medium of a fluorescent screen, which has a portion of its light transmitted through a lens to the recording sensitized surface. It is stated that this process is specially applicable for the purpose of recording Morse signals. The inventors have somewhat modified the original method by using a different current strength to signal each sign, and by the special arrangement of the cathode ray apparatus the variations of the current strength causes differences in the deflection of the rays in relation to a fluorescent screen. These variations in the light are transmitted to the recording surface by a lens and mirror, or a lens, diaphragm and mirror, which are so shaped that an image of the signal is recorded upon the sensitized strip. If necessary, the straight line deflections by currents of widely varying strengths may be substituted by a rotary deflection by means of a series of magnets variously energized through a corresponding number of conductors.

THE first sleeping cars built in Japan have just been completed.

A NEW BICYCLE HANDLE-BAR.

A novel manner of mounting bicycle handle-bars has been devised by Mr. Tacitus W. Gaillard, 346 South Fifth Street, Brooklyn, New York city, the special objects of the invention being to facilitate easy adjustment and to render the mountings of the bars secure. To the upper end of the fork-stem a tubular plug socket is fastened, upon the enlarged upper end of which a nut is screwed. The nut serves to clamp the fork-stem and the enlarged portion of the socket rigidly together. From the rear portion of the nut two parallel spring-fingers project downwardly, which are designed to receive a spring portion formed on the bifurcated upward extension of a clamp embracing the upper horizontal bar of the bicycle-frame. When the spring-fingers hold the extension of the clamp, the fork-stem is held steadily and prevented from moving except upon the application of positive pressure.

In the socket of the fork-stem is a plug which carries the handle-bars. The plug is provided with a spring-catch extending through a slot in the socket and through a corresponding slot in the fork-stem so as to engage a stud on the inner spring-finger. Thus the plug is removably held in place. By withdrawing the plug the removal of the handle-bars is facilitated.

The upper end of the plug has two ring-like extensions, between which are mounted the inner ends of the handle-bars, which ends are in the form of toothed segments. Meshing with these segments is a worm, the lower end of which is split, and the parts sprung out to form spring-fingers, which are held friction-tight in a cavity in the plug. The worm at its upper end is provided with a cap, which, when turned, rotates the worm and adjusts the handle-bars. No tool is required. The bars may be adjusted even when the rider is on the wheel.



THE GAILLARD HANDLE-BAR.

HANDLING ANTHRACITE COAL.

BY WALDON FAWCETT.

The story of the development of the anthracite coal field of Pennsylvania has always been full of attraction for students of commercial and industrial progress, both here and abroad, and its interest has been deepened as time has gone on and the apparent inexhaustibility of certain of the deposits has been demonstrated. There has been slight recognition, however, of how really an important a part in the evolution of the anthracite coal trade has been played by the improvement of facilities for the handling and movement of the fuel at every stage of its transit from mine to consumer. Nevertheless, in few industries has the value of the market been so entirely dependent upon an ability to place the commodity within reach of consumers. Finally, the many unique features of the system followed, notably the extent to which the railroads have controlled the mines and the operations of the pool which apportions the quantity of coal to be carried by each road, make the transportation of anthracite the most distinctive phase of the trade.

At the present time there is not a link in the entire transportation chain which connects the mine and the consumer wherein the most advanced and economical methods are not in force. The use of electricity about mines for lighting and other purposes has resulted in the development of electric locomotives for haulage purposes, and the coal is now drawn to the surface by electric engines of from two to fifteen tons weight. These locomotives have from one to three motors, ranging from ten to thirty-five horse power, and each is capable of pulling quite a train of the small cars in use in mines, at a speed ranging from six to ten miles per hour. Even the mine cars have undergone wonderful improvement during the past few years. Steel is largely employed in their construction and improved devices for quick dumping are fitted.

The coal is transported from the mines in the new type of pressed steel car, which is of about 50 tons capacity, and from 20 to 25 of these cars make up a train. In service on the coal-carrying roads are some of the largest and most powerful locomotives ever constructed. Some of these engines weigh close to 125 tons without the tender, and have a wheel base in excess of 24 feet. Locomotives of the type mentioned have a tank capacity of more than 7,000 gallons of water and a coal capacity of some 14 tons.

The railroads which enter the anthracite region are all operated under an agreement as to the basis on which the shipments of coal are to be divided between the various lines. The Philadelphia & Reading Railroad, for instance, which controls nearly a third of all the mining territory, is privileged to carry one-fifth of the aggregate output of the anthracite field. Another road is apportioned fifteen per cent of the total; several lines are entitled to one-tenth of the aggregate, and so on down to the lesser carrying lines, four or five of which only receive three or four per cent each of the whole yield.

The great bulk of the anthracite mined in the Pennsylvania district is shipped either to New York or Philadelphia, or else northwestward to Buffalo. These three cities are centers of the chief areas of consumption, and consequently serve as distributing points. A considerable portion of the coal consigned to Philadelphia or New York is reshipped, either by rail or coasting vessels, to Boston and other points in New England. Some coal goes south by the same means of transit, but it is a comparatively small proportion of the whole. The port of Buffalo, at the lower end of the Great Lakes, is the gateway through which passes the principal portion of the coal destined for western consumption. From Buffalo heavy shipments are made by lake vessels to Chicago, Milwaukee, Duluth, and other points, and there is also a very considerable traffic by rail.



CLAM-SHELL DREDGE UNLOADING COAL FROM BARGE.

The receipts of anthracite coal at Boston are somewhat in excess of those of bituminous, and both fuels reach the New England metropolis almost exclusively by water. As an illustration of the preference manifested by the coal shippers for the water route, it may be stated that every year during the past decade in the neighborhood of 2,000,000 tons of anthracite have been received at Boston by water, whereas in no year of which there is a record have the rail shipments exceeded 32,000 tons. The coastwise coal-carrying trade is carried on principally in wooden barges of from 800 to 1,500 tons burden. The construction of craft especially designed for this service has been carried on most actively during the past few years, and last year upward of half a hundred coal-carrying barges were turned out at the shipyards on the Maine and Massachusetts coasts. These barges, most of which are from 200 to 250 feet in length, are towed by powerful towing steamers. One of the best fleets of tugs in this service consists of six vessels, each 140 feet in length and fitted with triple-expansion engines, capable of driving the boat at a speed of 14 miles per hour. There are also numerous four and five-masted wooden schooners in the coastwise coal trade, and within the past few months a six-master had gone into commission. These vessels, all exceeding 300 feet in length, cost in the neighborhood of $100,000 each, spread 10,000 feet of canvas, and will carry 4,000 or 5,000 tons of coal on a draught of 23 feet.

Keeping pace with the other lines of development in the handling of anthracite is the improvement of the pier from which the coal is transferred to ocean vessels. As representative of modern facilities in this line there might be cited the largest of the coal piers of the Reading Railroad at Port Richmond, near Philadelphia. This structure which is probably the largest coal pier of the kind in the world, is 770 feet in length, 61 feet wide and 44 feet high above mean mud tide. The docks on either side have been dredged to a depth of 26 feet at mean low water, so that any craft may be accommodated. The pier is provided with four tracks and has four berths, two of which are provided with six chutes, each thus enabling four 1,500-ton barges or other craft to be loaded simultaneously. The approach to the piers, an earth-fill, is 1,150 feet in length, and the railroad cars, after being emptied, are run by gravity from the pier to the tracks on which the empty cars are stored. This pier, when taken in conjunction with the other facilities at the port, enables the Reading Company to ship fully 21,000 tons of anthracite coal in 24 hours.

In the loading and unloading of coal to and from vessels, and the rehandling of the fuel under various conditions, there are employed some of the most ingenious types of machinery known to the mechanical world. The primary form of apparatus for transferring the coal either to or from a vessel is what is known as the bridge tramway plant, consisting of long bridges with girders of steel or iron, mounted side by side on suitable rails so that they can be readily moved from place to place. Each machine operates over one hatch of a vessel, and is provided at its front end with a hinged apron of suitable length for extending the trolley tracks of the machine over the vessel.

The hoisting and conveying apparatus, known as the "trolley," runs along a track suspended from the bridge from the end over the vessel to the opposite end over the railroad cars or stock pile. For handling the anthracite there is used a self-filling and automatic dumping grab-bucket which will handle three-fourths of a ship's cargo without hand-shoveling. For shoveling the coal from stock piles to cars or boats there is employed an automatic shovel-bucket which requires no hand-shoveling whatever. One of these novel coal-carrying buckets will usually make a round trip from the hold of a vessel to the extreme end of



TYPICAL DOCK FOR LOADING COAL VESSELS.

the bridge and back again in a minute, a distance of six hundred feet in addition to the height of hoist. In actual work a rate of forty-five seconds per trip has been averaged for several hours. The cost of handling the coal by this method varies from seven-tenths of a cent to two cents per gross ton.

The same general form of bridge tramways are also the fundamental feature of the storage and rehandling plants. Balanced cantilever cranes are also, however, used to some extent in the rehandling of coal. At the works of the Bethlehem Steel Company, at South Bethlehem, Pa., for instance, a crane driven by steam, and having a reach of 365 feet, travels between two piles of coal 58 feet high. The coal is brought to the works in cars and dumped into great hoppers, from which it is drawn into tubs, hoisted, conveyed and dumped on the storage piles. The different sizes of coal may thus be kept separate.

At Cheektowaga, New York, and several other places in the United States, there are in service what are known as shed tramway plants especially designed for handling coal from vessels and stocking it under the same roof. The overhead runways on which the trolleys travel from the rear end of the building to vessel at dock front are movable from side to side, inasmuch as the upper supports of these runways are hung from wheels which move on tracks suspended on roof-trusses, thus enabling every portion of the storage space to be reached, and enabling the overhead tramways to move to any position along the front of the dock or in the sheds, to suit the hatch of the vessel or the stock-pile. By this plan the coal is never dumped more than two or three feet. A plant of this kind ordinarily has a storage capacity of a quarter of a million tons and will handle three thousand tons of anthracite per day.

Some coal is loaded into vessels from great bins built directly on the water front and some little distance above the deck of the vessel, so that the coal will slide readily through the adjustable chute through which it gains access to the hold. Finally, there are the various types of car-dumping machines, giant mechanical marvels, which in the space of a minute pick up a loaded coal car, overturn it, emptying its contents in the hold of a vessel and return the empty car to the railroad track. By the employment of one of these machines not only is rapid loading possible, but an entire cargo may be put aboard without its being necessary to move the vessel. With the addition of extra overhead cranes one of these car-dumpers has a capacity of ten thousand tons per day.

A Railway in Ashantee.

Kumasi, the capital of Ashantee, is to be brought into closer communication with England by the construction of a railway to the coast. The work is to be undertaken by a Liverpool firm, and already a party of twenty-seven engineers are on their way to the Gold Coast for the purpose of surveying the country. The line is to be 180 miles in length and of 3 feet 6 inches gage. The route to be followed is a very difficult one, extending through dense bush forest and over broken country. The engineers are to be assisted in the survey work by 1,700 carriers and laborers, to be dispatched and maintained from England. As the survey party proceeds, the work of construction will be carried out, operations being commenced at several places simultaneously. The great difficulty with which the contractors have to contend is the scarcity of labor and food, but it is anticipated that native labor will be forthcoming to the extent of about 10,000 men. The principal object of the railway is to develop the gold mining industry of the country. The land is very auriferous, and when the question of transport between Kumasi and the coast has been facilitated by the completion of this railway, the industry will be rapidly and extensively developed. Many of the West African gold mining companies are interested in the scheme, since it will then be able to reach the Ashantee capital within fourteen days from England.

Peculiarities of Siamese Music.

Profs. Stumpf and Neesen, of the Berlin University, have concluded some interesting experiments regarding the peculiarities of Siamese music. The Siamese musical octave differs from our own in the fact that it comprises seven equal intervals. The sounds, though perfectly harmonious, are somewhat curious. While the Siamese Court Troupe were at the Zoological Gardens in Berlin, these two professors decided to record these musical tones in their natural sound to such exactitude that the faintest variations might be clearly defined. In the earlier experiments the ordinary phonograph was employed, but was proved to be unsatisfactory, owing to the unpleasant constant rasping which always accompanies phonographic reproductions and which in this case destroyed the distinctness of the sounds. A telephonograph was then employed, and the results were all that could be desired. By means of this apparatus the sounds are so clear, and the graduations so faithfully recorded, that it is a difficult matter to distinguish between the actual recital by the troupe and its telephonographic reproduction.

Correspondence.

A Kerosene-fired Automobile.

To the Editor of the SCIENTIFIC AMERICAN:

In a copy of the SCIENTIFIC AMERICAN of November 17, I find you state that our boiler is fired with gasoline. The particular advantage possessed by this company over other makers of steam carriages is that we *do not* use gasoline as fuel, but in its place use kerosene. You will immediately recognize the importance of this difference, otherwise than which the item is correct, and we thank you for the same.

B. SHERWOOD DUNN, Sec'y and Treas.,
New York Motor Vehicle Company.

November 20, 1900.

A Popular Error.

To the Editor of the SCIENTIFIC AMERICAN:

It is generally entertained that the discharge of ordnance over or near the location of an animal body lying on the bottom or bed of a pond or river will, by the vibratory movement of the water, due to the impact of the discharge, cause the body to rise to the surface; and as a result of this opinion, the discharge of ordnance or of an explosive over a drowned body is usually resorted to, without any reference to the period of its immersion, the temperature of the water, or if the body is mutilated and to what degree; for if it has been but a brief period immersed, is much mutilated and the water is cold, such discharge or explosion over it is wholly and absurdly useless, as the specific gravity of the body is too superior to that of the water for it to rise.

The condition in which an immersed animal body may be raised to the surface by the discharge of ordnance or an explosive over it is this:

If the stomach of the body is intact, and the body not much mutilated, the temperature of the water and the period of its immersion is such as to evolve the gases of decomposition, the body increases in volume; and when its specific gravity is lessened to a degree that it is detained on the bottom only by molecular attraction, the disturbance of the water over it, whether by the action of the wheels or propeller of a steamboat in shoal water, or by the vibration of the water due to any impact on its surface, will disturb this adhesion with the bottom, and the body will rise to the surface. CHARLES H. HASWELL,

Board of Public Improvements, New York.

New York, October 18, 1900.

Iron Sailing Ships.

To the Editor of the SCIENTIFIC AMERICAN:

I have read with much interest Mr. Waldon Fawcett's article, published in your issue of September 22, on the subject of "American Sailing Vessels." We do not quite understand the author's statement relating to construction of metal ships, as follows: "Early in 1883 there was launched at the shipyard of John Roach, at Chester, Pa., the 'Tillie E. Starbuck,' a full-rigged iron ship, the first metal sailing ship built in the United States, and one of the first turned out anywhere in the world. The 'Starbuck' was also the first sailing vessel in the world to carry iron masts."

I witnessed the arrival at Liverpool about the month of May, 1870, of the American-built bark "Iron Age," which, as her name indicates, was built of iron. The vessel attracted great attention at the time among Liverpool shipping men, as she was said to be the first iron ship to be built on this side of the Atlantic. English-built iron ships were common enough at that date. In fact, the construction of a wooden ship in England was the exception, not the rule. Furthermore, I then saw vessels with not only iron masts, but large ships with every yard on board of iron. The American ship "Amity," of whose crew I formed one, had an iron main lower mast. The three lower masts were painted to imitate iron. I remember the exclamation of a St. George's Channel pilot when he boarded our ship: "Why, Captain, I never saw an American ship before with three iron lower masts."

The author makes another statement which I very much doubt: "The sailing vessels of recent construction, both wood and steel, have made some wonderful speed records, and have easily discounted the performances of that one-time pride of the shipbuilders, the 'Red Jacket,' . . . or of the 'Sovereign of the Seas.'" While the ships of to-day may be fine vessels, I do not believe that they can discount easily passages made by such clippers as the "Sovereign of the Seas," "Red Jacket," and "Flying Cloud," which vessels were built with view to speed, and whose fine models have never been surpassed. Except the fliers of recent date, very few steamers have equaled a famous run of the "Sovereign of the Seas," from noon to noon, on one of her passages to San Francisco.

I am greatly interested in American shipping, and would like very much to hear what passages are made by the big ships and monster schooners of to-day. Also would like to know number of crew carried by the five-masters referred to in article by Mr. Fawcett, and by that 5,500-ton (cargo capacity) six-master, which, I believe, has since been launched.

WILLIAM OWEN.

Panzos, Alta Verapez, Guatemala, October 20, 1900.

Automobile News.

Many accidents have occurred on account of the tires becoming detached from the steering wheels of automobiles, and too much attention cannot be paid to this matter.

The race from Berlin to Aix-la-Chapelle began August 30 and ended September 2. It rained heavily on the third day of the race, but fifteen machines succeeded in finishing. The net time of the winner was 14 hours 26 minutes and 22 seconds. This time was made with a motor tricycle.

The Touring Club of France is doing a great deal to help along the motor carriage cause by compiling lists of charging stations; and they are using their best endeavors to ascertain, where the plants are owned by private parties, whether they are willing to sell their current for recharging electric accumulators or not, and during what hours they are willing to do so, and a series of questions have been sent to all such parties.

A great improvement in motor tricycles is being introduced by the De Dion firm. The essential difference between the new and the old motor tricycle is that in the former the motor can be worked quite free from the machine, being started by means of the pedals separately, and afterward connected to the road wheels through the medium of a clutch. In the latter it is necessary in starting the engine to propel the machine forward at the same time—a fatiguing process.

The two automobile ambulances of Roosevelt Hospital are very handsome vehicles, and were donated to the hospital. There is room for three reclining patients, and eight can be crowded in if they are able to sit up. The batteries are charged in position, and as their radius of action is 25 miles, there is little danger that they will become exhausted, as the calls are seldom for a greater distance than two or three miles. Powerful brakes can bring the vehicle to a stop within a very few feet, while running at full speed.

Public automobiles in Paris have been taken in hand by the police, and now they are subject in common with cabs, etc., to the official regulations and tariffs. While the exhibition was open, the drivers of these vehicles charged the public prohibitive prices for their use, with the consequent result that they were not regarded with much popular favor. Now the maximum tariff for an automobile carrying four passengers is 40 cents for the "course," and 50 cents per hour inside the city. It is anticipated that this official control of the automobiles will encourage their more general utility in the streets.

Motor car owners using petroleum spirit will appreciate a new form of can for storing purposes, made by a German firm. It claims to be possessed of two valuable features. In outward appearance the can resembles those generally used, but inside there is a pipe which extends from the outlet to the bottom, and is pierced with holes throughout its entire length. Round this pipe is a gauze covering, which acts like the covering of the Davy miners' lamp in preventing flame coming in contact with the spirit. A new form of plug is used, which has a brass cap held in position by a fusible solder, which will melt in case of an outbreak of fire, and so allow any gas generated in the can to be liberated and prevent explosion.

Experiments were recently carried out in France for the purpose of ascertaining the quantity of fuel consumed by automobiles. The course extended from Suresnes to Meulan and back, a total distance of nearly 44 miles. Ninety-six vehicles competed in the trial. The premier position was secured by a moto-cycle, which piloted a quadricycle of 5 horse power, carrying two persons, and which only consumed about 4½ pints of fuel. The Comte de Chasseloup-Laubat, who traveled in a 24 horse power machine, covered the distance in 1 hour 43 minutes with a consumption of about one gallon. All the vehicles succeeded in covering the journey, and the results of the tests prove that the cost of running automobiles is considerably less than is generally supposed.

Infectious Diseases in London.

In the parish of Lambeth (London) within less than three weeks 105 cases of infectious disease were reported to the medical authorities, comprised mostly of typhoid and scarlet fevers. The investigations into the outbreak reveal the distribution of the contagion in a curious manner. The locality affected is inhabited mostly by the artisan class, the wives of whom, after washing their clothes, are in the habit of sending them to some neighbor or neighbors who possess a mangling machine, to have them wrung out or mangled. Consequently, the infected linen taken from one house to another to be so treated contaminated the mangle, which conveyed the infection to other non-infected clothes.

LIQUID AIR AUTOMOBILE.

Among the novelties displayed this year at the Automobile Show in New York city was an "auto" driven by liquid air. Any doubts that the public may have had as to whether this machine would operate were dispelled by nightly exhibitions upon the track in the center of the main hall, where the automobile, which is herewith illustrated, was run around the track and handled with the same facility as the steam and other automobiles.

There is no reason to doubt the ability of the machine to run; but upon the question of its range of operation, or "radius of action," if we may borrow the term, there is no further information than is contained in the printed literature of the company, which claims that in this particular machine enough liquid can be carried for a continuous journey of 50 miles. It is also claimed that the machine can be operated at a cost per mile which compares favorably with the cheapest forms of power which are used on other types of automobiles. In reply to queries, the operator stated that the Tripler Liquid Air Company would supply liquid air at 15 cents a gallon. As the capacity of the tank is 10 gallons, this would work out at a cost of 3 cents per mile.

As may be seen from the accompanying illustration, the carriage bears a striking resemblance to the carriages of the steam-driven type, and, in fact, it is neither more nor less than a locomobile, as far as the wheels, frame, body and engines are concerned, the only point of difference being the substitution of liquid air tanks and piping for the gasoline and water tanks and the boiler of the steam-driven machine. Bearing this in mind, the reader will understand that the novelties in the machine are contained in the accompanying perspective view of the liquid air equipment.

Immediately behind the seat, in the body of the car, is carried a copper storage tank for the liquid air. In front of it and beneath the seat is another copper tank, known as the coil expander; while in front of the vehicle, in the position occupied by the gasoline tank in the steam automobile, is another cylinder, known as the pressure equalizing tank. In the carriage illustrated the storage tank and expander are arranged side by side. The storage tank consists of an outer and an inner cylinder with an air space between them which is filled with a non-conducting material. The inner tank is filled with liquid air. Arranged along the top of the outer cylinder are four connections. The first of these (see perspective view) is a feed pipe, which passes through both cylinders and leads to the bottom of the inner cylinder, and is used to draw off the supply of liquid air for evaporation in the coil expander and ultimate use in the engines. The next outlet is a pipe which leads from a coil within the liquid in the inner cylinder to what is known as the quick-pressure valve. The third outlet is a pipe which leads from the top of the liquid air to the safety valve. The fourth connection is an ordinary inlet for charging the tank.

Liquid air, if exposed to the heat of the atmosphere, will evaporate rapidly, and therefore the inner tank has to be carefully insulated. Mr. Tripler claims that the insulation is such that it would take ten hours for the pressure within the tank to reach 100 pounds to the square inch. The normal pressure is maintained by means of a safety valve. The operation is as follows: To start the engine, the feed valve, whose hand-wheel is the rearmost of the two which are seen at the side of the carriage, is opened, admitting the liquid air to a coil of pipe within the expander. Here the liquid is evaporated by the heat of the atmosphere, and after leaving the cylinder, the air passes to what is called the radiator, a set of pipes which are arranged immediately below the two tanks. From the radiator, in which the air is brought up to the temperature of the atmosphere, it passes into a pressure equalizing tank, which, by providing a considerable volume of air, avoids the sudden variations of pressure at the cylinders which might result if the radiator communicated directly with the motor. A pipe leads from the equalizing tank directly to the motor. There are two gages on the dashboard, one of which records the pressure in the liquid air tank, and the other the pressure in the equalizing tank. A quick-pressure valve is provided on a pipe which leads directly from the pressure tank to the coil within the liquid air tank; when this valve is opened, air at normal atmospheric temperature, passing through the coil, produces rapid evaporation of the liquid and a quick rise of pressure.

Immediately in front of the valve controlling the supply of liquid air to the coil expander is a relief valve, by opening which air may be admitted direct from the top of the storage tank to the expander.

LIQUID AIR AUTOMOBILE.



LATEST ARRANGEMENT OF LIQUID AIR TANKS AND CONNECTIONS.

American Rolling Stock for South Africa.

Considerable excitement has been caused in English engineering circles by the announcement that large orders for the supply of new rolling stock for the South African and Transvaal railways, to supplant that destroyed by the Boers, had been placed in this country. A short while ago the various corporations on the Rand requested the military authorities, who are controlling the railways, to replace the rolling stock with the greatest possible expediency. The military Director of Railways replied that if the orders were to be dispatched through official circles, about one year would elapse before the contracts would be fulfilled, and under these circumstances he advised the corporations to place the orders themselves, and to hand it over to the military authorities upon its delivery until military operations had ceased. This course was adopted, and Messrs. Wernher, Beit & Company were intrusted with the placing of the contracts. When the principal English firms were approached, they replied that it was quite impossible for the material to be delivered for several months, since their output was already taxed to the utmost capacity. The American manufacturers were then approached, and they agreed to fulfill the contracts within three months, which was four months quicker than the earliest English promises. Their price was also about one-third cheaper than that of the English manufacturers. Under these circumstances it appears that part of the contract will be undertaken by the English manufacturers, and the remainder, owing to the urgency of the case, has been placed in this country. Some idea of the high pressure at which the English manufactories are working may be had from the fact that one railway company placed an order for 40 locomotives nearly two years ago, and they have not been delivered yet. The Midland Railway Company has just placed an order for 130 locomotives, divided among the four leading locomotive builders in the country. It will be remembered that it was this company which purchased several American locomotives from the Baldwin Works some months ago, but these engines do not appear to have given that complete satisfaction upon the English railways that was anticipated. Another order for railway rolling stock to the extent of $5,000,000 was placed with another prominent firm for immediate delivery.

Bacterial Light.

We are indebted for a good many things to the wondrous synthetic and analytical powers of micro-organisms. Bacteria are being utilized in the arts and manufactures and they promise soon to be the effectual scavengers of the offensive products incidental to the existence of human life, says The Lancet. Indeed, it would seem that the great species of bacteria around us present a variety of functions which doubtless could be turned to many a good account. Bad microbes we know there are, whose subtle operations set up the specific poison of disease, but it would indeed be a very odd circumstance if time should prove that the microbe can be so manipulated as to afford us artificial light. Yet there exists a microbe which when properly fed will grow and multiply enormously, emitting during its development a strange phosphorescent light. In the past we have been wont to look upon phosphorescence as a phenomenon due essentially to the presence of phosphorus somewhere. We now know that this is a mistake, for phosphorescence occurs in a very great number of instances in the entire absence of phosphorus. Phosphorescence is undoubtedly a manifestation of chemical or physical change, but the change of course may not always be due to the working of countless microscopic organisms. It certainly is in the case of the phosphorescence of the sea. In this case the phosphorescence is best when the sea is disturbed, and the maximum of light is emitted from the crest of a short, rapid wave or in the foam produced by some disturbance. This is due to the fact that the phosphorescent bacteria or photo-bacteria are much more active in the presence of an excess of oxygen. Indeed, the respiratory exchange or oxidation of the bacteria is the cause of sea phosphorescence, since if the micro-organisms be killed or oxygen be excluded the light is quenched at once, while on adding an abundant supply of combustible food-stuff such as sugar, the light is intensified. The glow of ordinary yellow phosphorus is, of course, due to direct oxidation without the agency of micro-organisms. The peculiar greenish glow seen upon stale haddocks and other sea fishes is produced by this remarkable photobacterium, and is in no way connected with the presence of phosphorus. It is possible to cultivate the phosphorescent bacteria so as to obtain a fluid which is very strongly phosphorescent. Thus by placing the flesh of fresh haddocks or herrings in a two to three per cent solution of common salt and keeping at a low temperature—about seven degrees above freezing—it will be found that after a few days not merely the fishes, but also the whole of the liquid in which they are immersed, give off a pale greenish light which becomes much more brilliant if a little sugar be added. Pure cultures may thus be obtained exhibiting such a strongly phosphorescent light that by protracted exposure they may be photographed by their own light. It is not possible to say whether the culture will ever be carried to such a pitch that the vessel containing it may be used with advantage as a street lamp or a lamp upon our tables or a Chinese lantern at our garden parties. But the wonderful functions of bacteria are many, and the possibilities of using their powers multifarious.

A New Electric Fountain.

A new electric fountain has been devised. The idea is to combine tableaux-vivants with a display of brilliantly illuminated pouring water. A fountain of this kind has been built at Heine Park, Kansas City. In the center there is a platform for persons who are to impersonate various statues and groups. Outside of this circular platform are jets which are illuminated by electric lights. The space in the center being dry, pyrotechnic display will be used in conjunction with the aquatic figures.

THE MAKING OF PICTURES IN WOOD.

Salem, Mass., counts among its residents a Mr. E. C. Larabee, whose peculiar art it is to make beautiful pictures from bits of wood, so skillfully that even a practised eye cannot always discover what material has been used. In the simplest method of constructing these pictures two panels of wood, a glass table which can be inclined at any angle, and a Fleetwood jig-saw are employed.

A pen and ink drawing of the picture to be reproduced is glued on a panel of wood $\frac{1}{16}$ of an inch thick. To the panel a wood backing of the same thickness is secured. Both pieces of wood are then sawed along the lines of the drawing. The sawed portions of the top piece are then removed, and the spaces thus formed are filled by the corresponding sawed portions of the lower panel. The finer the saw used, the less kerf will there be.

The reproduction of a picture in colors requires the most consummate skill. It is no mean task to arrange several hundred minute pieces of colored wood so that the tints will blend to produce the effect of an oil painting, without the slightest rigidity and without the faintest suggestion that wood has been employed. In order to secure a good effect, Mr. Larabee assures us that he has spent five hours seeking in his collection of rare woods a piece which was inlaid in five minutes.

The wood is not stained or in any way colored, but is employed in its native tints without any preparatory treatment. Much of the wood comes from parts of the world rarely visited by travelers. A certain sacred tree which grows in India and which formerly was employed only in the making of idols has furnished Mr. Larabee with many a precious bit. Rare woods from Cuba, Porto Rico, and the Philippines found their way into a portrait of President McKinley which now hangs in the White House. The "Parisian Street Musician" reproduced herewith is composed of many woods but little known. In the coat, for example, are pieces of Madagascar black ebony; the hat contains striped ebony from the River Congo; the trousers are inlaid with Alabama persimmon; the eyes are composed of English white holly; the cravat and cuffs consist of American maple; part of the vest is of gold and satin-colored babbool from India; the face and hands are of cream-colored olive-wood from Palestine; the shirt is made of cream quince from Massachusetts; the material of the violin-bridge is Cuban pepil; and parts of the trousers are made of ashen gray impee from Manila.

In making a picture ten by fourteen inches in size from four to six dozen imported Swiss saw-blades are worn out, and from six hundred to eight hundred pieces of wood, one-sixteenth of an inch in thickness, used. Often the sawing of the wood exacts the utmost patience on the part of the artist. Cocoabollo, for example, contains a gum which clogs the teeth of the saw so quickly that not more than six cuts at a time can be made. Some of the most beautiful woods are so rich in oil that they must be baked and partly dried in order that the glue may hold.

Governmental Supervision of Forestry.

During the past year considerable work has been done in private tracts under advice from the Division of Forestry of the Department of Agriculture. In October, 1898, an offer was made to give advice and assistance to private owners in handling their woodlands. This year applications were received from owners in thirty-five States, and the total area covered with these applications was about 1,600,000 acres. Sixty students have taken up forestry as a profession under the instruction of the Division of Forestry, and they have been at work in the forests of the various

"A PARIS STREET MUSICIAN"—PAINTING REPRODUCED IN INLAID WOOD.

States during last summer, under the supervision of trained foresters. The results are of great value. All the expenses of the students are defrayed by the government while the men are in the field. The ultimate object is to prepare the students for service in the Forestry Division of the United States government. At the present time the call for experts is comparatively slight, but is increasing with great rapidity.

THE NEW ARMORED CRUISERS OF THE "CALIFORNIA" AND "MARYLAND" TYPES.

No feature of our latest naval programme shows more forcibly the impress of the lessons learned by our late war with Spain than the new armored cruisers now nearly ready for the bidding contractors. Our new battleships are typically fine craft and thoroughly up to date; but it is the armored cruiser that marks most sharply the pace we have cut out for ourselves. The armored cruiser, besides being the eyes and ears of the fleet, will take its place if need be in the line of battle. The "New York" was an advance upon her British prototype; the "Brooklyn" was an improvement; but the "California" and her class are really second-class battleships with armored-cruiser speed, any one of which against the combined batteries now on the "New York" and "Brooklyn" could hold its own with a very fair prospect of giving the two other ships a pretty bad drubbing. Such is the rapid rate of naval development to-day. The six ships in question were provided for by the acts of Congress of March 3, 1899, and June 7, 1900, respectively, three ships being appropriated for at each time; and those of the earlier act are required to be sheathed and coppered, while the last three allowed for were not so specified. Should authority be given to sheathe and copper the latter vessels, the contractors must stand ready to do so.

The general dimensions of the sheathed and coppered ships are as follows:

Length on load water-line	502 feet.
Beam, extreme, at load water-line	70 "
Trial displacement, about	13,800 tons.
Mean draught at trial displacement, about	24 feet 6 inches.
Greatest draught, full load	26 " 6 "
Coal carried on trial	900 tons.
Total coal bunker capacity	2,000 "
Feed water carried on trial	75 "
Speed not less than	22 knots.
Maximum indicated horse power	23,000

The only dimensional particulars in which the unsheathed ships will differ from the others are a maximum beam six inches less and a lighter trial displacement by 400 tons; in other respects they are alike.

The ships will have the usual extensive bulkhead system and close water-tight subdivisioning common to all modern fighting ships, and the double bottom will be so arranged that a reserve supply of fresh water may be carried there. The ships will have both docking and bilge keels. The main deck will be the only wooden deck, the others being laid with linoleum; and the use of wood will be restricted to the last degree, all of that within the vessels being fire-proofed.

The fighting positions and the "vitals" will all of them be sheltered behind walls of Kruppized steel, and the arrangement of armor protection will be as follows: First, a water-line belt 7 feet 6 inches wide extending from bow to stern. The belt carries its maximum thickness 4½ feet from the top down, whence it tapers to the armor ledge. For a distance of 244 feet amidships, the armor will have a maximum thickness of 6 inches and a minimum of 5; thence to the bow and to the stern the belt will have a uniform thickness, top and bottom, of 3½ inches. For a distance of 232 feet amidships, above the water-line belt and up to the main deck, the sides will be reinforced by 5-inch armor; transverse bulkheads, turning inboard at the ends of this side armor, will complete the central casemate housing the ten 6-inch guns. These transverse bulkheads will be 4 inches thick. The protective deck will be continuous from bow to stern; on the flat it will be 1½ inch thick and on the slopes 4 inches thick. Above this protective deck, a cellulose belt 3 feet thick will be worked along the sides from one end of the ship to the other. It is required that the water-line armor belt be so placed that at least a foot of it will be out of water at deepest load draught.

The armament will consist of: A main battery of four



Drawing by R. G. Skerrett.

NEW ARMORED CRUISERS OF THE "CALIFORNIA" AND "MARYLAND" TYPES.

Length, 502 feet. **Beam,** 70 feet. **Displacement,** 13,800 tons. **Speed,** 22 knots. **Bunker Capacity,** 2,000 tons. **Armor:** Belt, 6 inches; deck, 1½ to 4 inches; gun positions, 6 inches. **Armament:** Four 45-caliber, 8-inch; fourteen 50-caliber, 6-inch; and eighteen 50-caliber, 3-inch rapid-fire guns; thirty smaller guns. **Torpedo Tubes,** 2 submerged. **Complement,** 822.

45-caliber, 8-inch, breech-loading rifles and fourteen 50-caliber, 6-inch, breech-loading rifles; and a secondary battery of eighteen 14-pounders, twelve 3-pounders, four 1-pounder automatic guns, four 1-pounder single-shot guns, two 3-inch field guns, two machine guns, and a half a dozen small caliber pieces for boat service. There will be two submerged torpedo-tubes, to be placed on the broadsides pretty well forward. The 8-inch guns are to be mounted in two balanced elliptical turrets on the main deck forward and aft of the superstructure. These turrets will be generally 6 inches thick with slanting faces ½ inch thicker. The turrets are to be controlled electrically, and are to fire through arcs of 270 degrees. The rate of ammunition supply is one complete round of powder and projectile to each electric hoist every fifty seconds.

The four 6-inch guns mounted on the main deck are to be placed in sponsons at the four main corners of the superstructure, and are to fire through arcs of 145 degrees—the forward ones from dead ahead aft, and the after ones from dead astern forward. These guns are protected by 5-inch armor. The ten other 6-inch guns, five on each broadside, are to be placed amidships on the gun deck—the forward ones firing dead ahead, while all the other guns on each side will have arcs of fire of 110 degrees, and will be arranged to house within the side line. These guns will be separated by 2¼-inch splinter bulkheads. The ammunition hoists will be run by electricity, and are to supply each 6-inch gun with three complete rounds every minute. The 14-pounders will be mounted on the gun deck and up in the superstructure, two forward and three aft of the 6-inch battery on each side, and four on each broadside between the 6-inch guns up in the superstructure. The 3-pounders are to be mounted on the superstructure deck and on the bridges, while most of the 1-pounders are to fill the military tops. Each 14-pounder is to be supplied six rounds a minute, while the 3-pounders are to have ten.

The firing stations for the torpedoes will be sheltered from the reach of 6-pounders and lighter pieces, and are to be located above the torpedo tubes. The conning-tower, located at the fore end of the superstructure, will be of steel 9 inches thick, and the signal tower, located at the after end of the superstructure, will be of steel five inches thick. The pilot-house will be of bronze. All magazines are to be carefully insulated, and certain of them are to be chilled by the refrigerating plant. All are also to be easily susceptible of instant flooding.

Because of the extensive application of electricity, the ships will carry pretty large generating plants, having a total output from the seven units of 6,250 amperes at 80 volts—power enough to run all the ammunition hoists, work the turrets, drive some of the ventilating fans, run the machine shop, and furnish power for the steam laundry which is to do the major share of the officers' and crew's washing. Owing to the high freeboard of the ships and to the fact that it is carried uniformly from bow to stern, very excellent accommodations will be provided for the officers and enlisted men, of which the complement will consist of: 1 flag officer, 1 commanding officer, 1 chief of staff, 20 ward-room officers, 12 junior officers, 10 warrant officers, and 777 enlisted men, a total of 822 persons.

The ships will have twin screws, driven each by its own triple expansion engine of the four-cylinder type. The high-pressure cylinders will be 36 inches in diameter, the intermediate-pressure cylinders will be 59½ inches in diameter, and the two low-pressure cylinders of each engine will be 69 inches in diameter. They will have a common stroke of 45 inches, and the engines will make about 133 revolutions when developing the maximum indicated horse power of 23,000. Steam will be supplied by 30 boilers of the straight-tube water-tube type placed in 8 water-tight compartments. They will have a combined grate surface of at least 1,590 square feet and a total heating surface of quite 68,000 square feet. The four funnels will rise 100 feet above the grate bars. The normal reserve of fresh water will be 150 tons—just half of that carried on trial, and, excepting coal, the trial displacement will call for two-thirds of all other stores.

The ships will carry ammunition enough to put up a good long fight; 500 rounds being allowed the 8-inch guns, 2,800 rounds for the 6-inch guns, 4,500 rounds for the 14-pounders, 6,000 rounds for the 3-pounders, and a pretty liberal supply for the rest. Provision is to be made for closing many of the water-tight doors automatically, i. e., from a single controlling station, and every care has been taken to minimize the consequences of accident or injury. Three years is the maximum time limit for construction, and the maximum limit of cost is $4,000,000 in the case of the ships of 1899 and $4,250,000 in the case of the ships provided for during the present year.

We have ample reason to be proud of these latest products of our naval designers; and in either peace or war they are bound to command a wholesome respect.

THE POLLAK PRIZE FOR LIFE-SAVING DEVICES.

The competition for the Pollak prize offered for the best life-saving devices brought together an extensive exhibit, which was contained in the Navigation building of the Paris Exposition. Mr. and Mrs. Pollak, of Washington, D. C., were among the passengers lost on the ill-fated vessel "Bourgogne," and their heirs decided to found a memorial prize of $20,000 to be awarded for the life-saving devices which, in the opinion of a committee of experts, would be the most efficient in preventing such disasters or in saving the passengers in case of shipwreck. Circulars were issued by the United States government stating the conditions of competition, and the Paris Exposition was selected as the most appropriate place for the assembling of a collection of this kind. The French government and the different foreign commissioners also issued circulars in their respective countries calling for inventions of this nature. As a result, more than four hundred competitors from Europe and America sent models of life-saving devices, or plans and descriptions, and these were seen in the Navigation building, near the Seine. An international committee of naval experts was appointed, including prominent naval officers or constructors from different countries, among whom may be mentioned Lieutenant Sims, late United States naval attaché at Paris; Commander Clavaud, director of the French life-saving society; Captain Siegel, German naval attaché at Paris; Rear-Admiral Naoumoff, chief inspector of the Russian life-saving society; Signor Pasella, naval constructor, professor at the Italian school of naval architecture; M. Couvert, president of the Chamber of Commerce at Havre; Captain Wallenberg, of the



The Roper System of Launching Lifeboats



The Roper Life-Raft in the Act of Launching.

Some of the American Inventions.

Individual Life-Saving Appliances.

COMPETITION FOR THE POLLAK PRIZE OF $20,000 AT THE PARIS EXPOSITION.

Swedish navy; Captain Nepean, director of the English life-saving society, etc.

According to the rules, the jury had the right to award the whole of the prize to one person or divide it among several competitors; the awarding of the prize was not obligatory, and it could be withheld for a future competition. As a result of the examination of the different systems, the jury found that the appliances designed by Mr. Leopold Roper, an experienced English naval architect, came the nearest to a satisfactory solution of the problem; as, however, the final solution had not yet been reached, and there was still room for considerable improvement, the jury decided not to award the whole of the prize at the present contest. The sum of $2,000 and a gold medal was awarded Mr. Roper, as his system was considered by far the best in the present series. A description of these devices will be useful in showing what lines should be followed by inventors who wish to enter the next competition for the prize. These devices include, first, an improved system of life-boats and davits, and second, a life-raft which the committee think is the most valuable.

The system of life-boats will be readily understood by referring to the figures, which represent the working models shown in the section. The first of these shows the boat suspended from the davits in its normal position. The davits are of steel channel and are light and strong; they are pivoted below the deck and carry in the rear a pivotal support which is attached at the level of the deck to a guide-piece which slides back and forth in a hollow deck beam by means of a large screw. This screw is operated by a winch at the side, worked by one man. When the winch is turned, the davits rise, being pushed up by the rear arms. The boat is then ready to be lowered. This is done by a second winch in a corresponding position on the other side, which unwinds the steel rope which supports the boat, and the boat may thus be lowered to either of the decks and to the water in a very short time by the man in charge. The use of a single steel rope is a great improvement over the ordinary block and tackle; when not in use it is for the most part inside the davit, and consequently well protected from the weather, and there is no complicated arrangement of ropes to become tangled up when the boat is released. As both ends are let go at the same time, there is no danger of tipping up the boat and throwing out the occupants, as often happens. The advantages of such a system over the ordinary davit with block and tackle are at once apparent. The boats themselves were also recommended by the committee. They are built of steel and are lighter and stronger than the present wooden ones, besides not being subject to warping or leaking when exposed to the weather. They are made with double bottom and a series of air-tight compartments, and are one-fifth lighter than other boats of the same size. On account of their great buoyancy they may be fully crowded with passengers without danger of sinking. The "Campania," of the Cunard line, has been fitted with twenty boats on this system, and it is of interest to compare the figures with relation to the ordinary boat. On the "Campania" the weight of each boat of the ordinary type is 3½ tons, making a total of 70 tons. Each boat carries 60 passengers, or in all 1,200 persons are taken. The forty davits each weigh 2,600 pounds, or a total of 52 tons, and the weight of boats and davits is 122 tons. To lower all the boats, allowing 10 men for each, requires 290 men. By Roper's system, each boat weighs 2½ tons, or 50 tons total; the boats carry 110 persons each, providing for 2,200 passengers. The 40 davits weigh each 1,800 pounds, making 36 tons, or for the whole system, 86 tons. Two men are required to lower the boats, making only 40 men. It will be seen that 2,200 persons are provided for, against 1,200, and the system weighs 86 tons against 122 tons; the greatest advantage is in the small number of men necessary, or 40 against 200 by the old system. For these reasons the committee consider that this system of life-boats is a great advance upon the present system and recommend its adoption; it is, however, the life-raft designed by Roper which is considered to be a step in the right direction toward solving the problem.

Our second engraving shows the appearance of this raft, which is large enough to carry 600 persons. It is built of steel, with double bottom, and divided into compartments forming air chambers; in some of these supplies of water, provisions, etc., are carried. The raft is supported normally above the deck and serves the purpose of the captain's bridge, it thus does not take away any extra room, and costs but little more than the ordinary form of bridge, this being estimated at $2,000. The raft is supported on each side by a heavy angle-piece, serving as a guide, in which it may slide back and forth by sets of rollers placed at intervals along the bottoms and sides. These cross-pieces are supported at each end by solid uprights, which are firmly secured to the deck; the cross-pieces are held in place by a simple clamp device, which may be instantly released by moving a lever. In case of shipwreck the raft is loaded with passengers, and a man at each side releases the clamp, thus lowering the guide-pieces at that end, and the boat rolls out by its own weight to the water's edge. This movement is shown in our engraving, where the oblique position of the guides will be observed, also a second guide-piece in front, which normally forms part of the upright support, but is now lowered, and serves to guide the boat into the water. As will be seen, the whole arrangement is one of great simplicity and not likely to get out of order, and can be operated by a few men. In the compartments may be placed provisions for six days, besides sails and tackle, etc. The buoyancy of the raft is amply sufficient to keep it afloat even if some of the compartments should become damaged. It may be remarked that the raft may be utilized under ordinary circumstances for landing troops, horses, etc., and can give good services in this way. This system of life-rafts has been tested practically upon H. M. S. "Polyphemus," which was provided with two of these rafts, of practically the same design as shown in the present model; the trials showed that they fulfilled all that was claimed for them, as each raft contained 200 men with supplies, etc., and the launching was carried out in about 45 seconds.

The committee are decidedly in favor of life-saving en masse, and for this reason have approved Mr. Roper's life-raft as the only device in the present competition which answers to this idea in a practical manner. Most of the inventions, outside of individual life preservers, seem to have been made by persons who had but little practical knowledge of the conditions to be met with. It should be observed that all appliances which require skill in putting together at the moment of shipwreck are almost valueless, as there is generally not sufficient time to manipulate such devices, and the crew of a transatlantic liner, composed as it is of untrained men, many of whom may have been taken on board at the moment of starting, cannot be depended upon for any great service in this connection; devices must be looked for which take only a few men to operate for the saving of a great number of passengers, such as the large life-raft. The type designed by Roper is, however, somewhat large, as a heavy raft for 600 persons might cause some trouble in getting started; by using a small-sized raft and increasing the number, a more satisfactory result would, no doubt, be obtained. The committee do not favor the system of water-tight compartments for vessels, on account of the cost and diminution of the capacity of the vessel; in a severe collision, such as that of the "Bourgogne," the system would not have availed much. Another point that should not be overlooked is that a vessel sinks end first, and accordingly many of the detachable deck-houses and other similar devices would fail to work. As it was not to be supposed that a first competition would be entirely successful, it has been decided to hold a second in the autumn of 1901, and a circular to that effect will be issued probably before the end of this year; it may be held at some point on the English Channel, as this will give a favorable opportunity to try some of the devices in actual practice.

Out of the great number of devices a few have been selected for illustration as showing the general character of the exhibit.

One of the views shows some of the American inventions. To the right are two systems of improved davits and life-boats, and in the center is a model of a "marine brake," consisting of a large plate which is pivoted against the side of the vessel and may be swung out at will, thus slowing up the vessel by the resistance-surface it offers. Of the two larger models below, that to the left shows a type of inclosed life boat for a great number of persons, built of copper, and the second model represents a method of lessening the effect of collisions by surrounding the vessel with a series of rubber buffers. On the wall are several rubber garments which are inflated with air, etc. A great part of the exhibit is made up of individual life-saving devices, which are inflated or made of cork, air cylinders, etc. One view shows a number of these devices. The figure on the left has garments which may be inflated, also a rubber air belt, and next it is a vest made of cork and chamois skin. The two figures in the center carry a kind of long life-belt made of a number of sections of impervious material stuffed with a mixture of lamp-black and cork, and near it is a belt made up of semi-cylindrical air-chambers of waterproofed leather.

Two English systems of water-tight doors for the compartments of vessels are shown. The door seen on the left is normally held open by a catch which is released at will by an electro-magnet or a hydraulic cylinder and the door swings shut and is locked automatically. In the second system the doors slide into place, forming a water-tight joint, and all the doors of the vessel are controlled from a central point. Either hydraulic pressure or electric motors are used for the closing. The motor on the left pushes the door into place by means of a long screw, which is turned by gearing and works in a nut on the door. On the right is a hydraulic system for accomplishing the same movement; above and below are the cylinders whose pistons act upon the door, and it is closed or opened by sending the pressure into the forward or rear pipe. Both systems are worked from a central point either by a series of valves or electric switches.



FRONT AND SIDE ELEVATIONS OF ELECTRIC CLOCK.



ELECTRIC CLOCK RUN BY EARTH PLATES.

ELECTRIC CLOCK RUN BY EARTH PLATES.

Our occasional contributor Mr. N. Monroe Hopkins has prepared with a great deal of care an article on a new electric clock of his devising, which is well-nigh perpetual in its action, besides being accurate and practically noiseless.

The general appearance of this clock is shown in the perspective view, and much of the detail is given in the outline side and front elevations. The design and its carrying out are so novel and attractive that we have given in the current SUPPLEMENT the author's article in full, with many additional illustrations, the whole being sufficiently explicit to enable a careful workman to make it. The clock shown in the perspective view was mounted on a suitable base and inclosed in glass.

The back plate, *G*, which supports the entire mechanism, is secured to the caps of the pillars, and has, at its center, the knife-edge bearing of the pendulum. To this back plate are secured four magnetic spools, *A*,

at equidistant points, and a brass spider, to which all the parts of the pendulum are attached, has a knife edge which rests in the groove in the support projecting from the back plate, *G*. The knife edge and its support are hardened in cooled mercury, thus rendering them practically indestructible by wear. To the arms of the spider are attached four curved bars of soft iron, which in the regular operation of the clock are drawn into the magnetic spool and released once every second. To the front of the spider is secured a frame, *F*, from which is suspended the pendulum weight. The weight in this case consists of a rod and two cross-arms, and two tubes filled with mercury which rest on the lower cross-arms, the upper ends of the tubes being supported by screws passing through the upper cross-arms into the tubes.

The frame, *F*, has an arm which extends upwardly and carries two screws, the one on the left being platinum-pointed. The arm of the hard rubber hammer, *D*, is pivoted to the frame, *F*, at the center of oscillation and carries a platinum point capable of making an electrical connection as the hammer, *D*, swings over and carries it against the platinum-pointed screw. The magnetizing coils are connected in series and the terminal wires are connected one with the arm of the hammer, the other with the platinum-pointed screw.

Above the pendulum, and behind the dial, is supported a train of gears which moves the hands and is moved by the large pin wheel, which takes its motion from a pawl vibrated by the pendulum. A second pawl prevents the pin wheel from moving when the actuating pawl is drawn down for a new movement.

The clock receives its current from an earth battery consisting of ten pairs of zinc and copper plates, each twelve by eighteen inches, buried in earth at a sufficient depth to be kept constantly moist, and connected with the clock by rubber-covered wires. With a battery of this kind the clock will run until the plates are destroyed. If desired, it may be operated with four to six cells of gravity battery.

The various parts of this clock must be perfectly balanced, and the regulation by changing the length of the pendulum must be done with considerable care.

Notes on the National Academy of Sciences Meeting.

BY WILLIAM H. HALE.

Many pictures were shown of the forms of cephalopods from their first appearance, which was probably in the Potsdam, certainly in the Quebec group, below the Chazy, which is the base of the Ordovician, down to the present time. Also pictures of the development of individuals from embryonic to senile stages.

Also the development of many morphological characters was shown in a sequence of formulas as a mathematical statement. The development of these animals, both secular and individual, was shown to be a harmonious chapter of the grand evolution of life, precisely parallel to what Cope has shown for vertebrates and Beecher for branchiostomidæ. Space limits me to mention a single cycle, the change of form. Beginning with straight shell, curled forms follow. Very late, they straighten out again. This connects ammonites with the young of orthoceras. Every bilateral part of the shell is affected by this coiling and uncoiling, whereas the median line is not.

Forms acquired late in life appear earlier and earlier in the embryo, till finally they disappear, owing to the superior power of the embryo. This is called tachygenesis.

The embryo of straight form is coiled, recalling the adult form of its ancestors.

In old age there is a gradual decrease of acquired characteristics.

When a new form is developed late in life, it goes through the same series of changes as the embryo.

It is not till many phases of evolution have occurred that old age shows any distinctive characteristics. Thus in the Silurian it is difficult to find any animal which shows any effect of old age.

After certain forms have developed there is a reversion to simpler forms. Just as old age becomes a second childhood, so forms of earlier geologic age reappear today. The life cycle of the middle group corresponds to the secular cycle of the entire group.

IT seems impossible, when electric traction has so firmly established its superiority over any other means of power for the propulsion of street cars and light railways, that the obsolete cable system should be decided upon in a large city like Edinburgh (Scotland). At a recent meeting of the Municipal Council of that city the question of erecting a new cable power station for a section of the tramway was discussed. One councilor, who is a firm advocate of the cable system, emphatically averred that Edinburgh possessed the finest tramway system in the world, and by dint of persuasive eloquence succeeded in carrying the vote favoring the erection of the cable station. This will involve an outlay of $100,000, a sum sufficient, as another councilor remarked, to convert the whole section for which the station is being erected to the overhead trolley system.

The Current Supplement.

The current SUPPLEMENT is No. 1300, the first number having been issued January 1, 1876, and as the paging has been consecutive throughout this long period, the last one bears the number 20846. The front-page engraving is an excellent portrait of Giuseppe Verdi. "High Water Protection Methods of the Lower Mississippi River" is by William Joseph Hardee. "A Graphic Description of the Efficiency of Naval Guns" is a most important technical article. "Salt Water Aquarium at the Paris Exposition" illustrates the most modern type of aquarium. "An 'Electric Earth Clock' and Its Construction" is by N. Monroe Hopkins, and is accompanied by working drawings.

Contents.

(Illustrated articles are marked with an asterisk.)

Ashantee, railway in..... 342
Automobile, liquid air*..... 343
Automobile news..... 342
"California," cruiser*..... 344
Clock, electric*..... 346
Coal, anthracite, handling*...337, 341
Coherers..... 339
Cruiser "California"*..... 344
Disease, infectious..... 342
Error, popular 342
Fire, fighting with wine*..... 340
Forestry, government supervision of..... 344
Fountain, electric, new..... 343
Guns, efficiency of..... 338
Handle bar, bicycle*..... 341
Heavens in December..... 339
Life saving devices, Pollak*..... 345
Light, bacterial..... 343
National Academy of Sciences.. 347
Pictures on wood, making of*... 344
Receivers, telegraph, photographic. 340
Rolling stock, American, for South Africa..... 343
Sailing ships, iron..... 342
Science notes.. 339
Shipbuilding, Pacific coast..... 338
Siamese music, peculiarities of.. 342
Thunder and lightning, artificial*..... 340
Traffic, congestion of..... 338

RECENTLY PATENTED INVENTIONS.

Agricultural Implements.

CULTIVATOR.—FERGUSON G. BRIGHT, Commerce, Mo. The cultivator has two shovel-beams sustained at their front ends. A rod extends rigidly between the rear portions of the shovel-beams. On the front portions of the shovel-beams a foot lever is mounted, each having a return bend permitting the rod to pass beyond each side of the longitudinal line of the foot-lever. Chains or other flexible connections pass between the foot-lever and the shovel-beams and run over the axle of the machine. The chains serve to limit the downward movement of the beams, and consequently the depth at which the shovels enter the ground. The foot-levers, when pressed down, will throw the beam up and disengage the shovels from the ground.

HORSE-HOE AND CULTIVATOR. — EDWARD J. BRYAN, 1504 Twentieth Street, South Highlands, Birmingham, Ala. The inventor provides an improved mechanism by the use of which he is able to bar off or scrape to narrow ridges the beds forming the row; to chop or hoe the desired space out of the row of plants; to dirt the plant after hoeing, means being provided to prevent the covering of the plant; and to plow, pulverize, cultivate, or rake the full width of the row.

PROCESS OF AN APPARATUS FOR PROTECTING TREES OR VEGETATION AGAINST COLD.—JAMES F. TUCKER, United States Department of Labor, Washington, D. C. The inventor has observed that tender vegetation on the south shore of a body of water usually escapes the blighting effect of frost. In Florida the deep-water rivers and lakes are fed by springs which contribute to the heat treasured up from the long summer months, so that during a cold spell, the air is brought in contact with a body of water at a relatively high temperature. A cloud of fog or vapor is thus produced, completely enveloping the locality to the south and east and protecting the vegetation. The present invention comprises means for making an artificial fog in the orchard or over the ground to be protected. The essentials are heat and moisture applied in such a way as to make sensible the latent heat as an adjunct to the heat actually supplied.

Electrical Apparatus.

BARBER'S ELECTRICAL APPLIANCE.—MARTIN SCHUPNER, Nyack, N. Y. Mr. Schupner has devised an improved electrical apparatus arranged to permit a barber or other operator to apply a current of electricity of desired intensity to the human body, mainly, however, to treat the scalp for strengthening, drying, or assisting the growth of the hair.

Engineering Improvements.

STEAM-TRAP.—GEORGE H. GROTE, St. Louis, Mo. The object of the invention is to provide a steam-trap with a simple means for regulating the tension-spring, whereby it is made unnecessary to shut off or take the trap apart to adjust the spring, thus saving time and expense. A diaphragm divides the trap-casing into upper and lower chambers. The inflow of water acts upon the diaphragm in order to operate a valve, so that the proper level may be attained. The action is entirely automatic.

Mechanical Devices.

GAS-PRESSURE REGULATOR.—THEODORE HAHN, Kötzschenbroda, Saxony, Germany. The use of gas-engines with an intermittent gas-supply is accompanied by the disadvantage that in the gas-mains variations in pressure are perceptible. Ordinary gas-governors imperfectly overcome the difficulty, for the reason that only a single gasometer-hood is employed. According to the present invention the gas, before passing into the gasometer-hood which controls a gas-supply valve, passes through a special pressure-regulator loaded in conformity with the friction of the gasometer-hood and in such a manner that the gas can pass into the gasometer-hood without perceptible impulses occurring in the regulator and gas-main.

ROLLER-BEARING.—JOHN S. GODFREY, Harrington, Wash. A casing has the ends of its inner wall curved inwardly. Guide-rollers extended through the casing are supported by a cage. The ends of the guide-rollers are rounded. Antifriction-rollers are supported by the guide-rollers and have rounded ends. The rounded ends cause very little friction.

TYPE-WRITER.—MANUEL S. CARMONA, Mexico, Mexico. The type-writer is an improvement on Mr. Carmona's previous inventions in machines in which a small number of keys is employed which either singly or in combination govern the action of a type-locating mechanism and of a printing device. The present invention provides means for locating the type, which means are positive in action and are not liable to deteriorate by wear. The arrangement of parts is so simplified that the movement of the carriage will be relatively slight. An improved mechanism is furnished for effecting the impression.

SAW-FILING MACHINE.—GRANVILLE BARTLETT, 347 Trumbull Avenue, Detroit, Mich. The machine is of that form in which a pair of clamp-bars hold the saw-blade with its teeth uppermost and a sliding carriage or guide frame for the file-holder is arranged to be moved longitudinally along the clamp-bars and has guide-seats to receive the file-holder in its reciprocating movement across the saw. The present invention consists in the peculiar construction of the saw-clamp; the peculiar construction of the file-holder guide or carriage; and in the peculiar means for adjusting the angular position of the file in regulating the inclination of the teeth to be cut.

PHOTOGRAPHIC SHUTTER. — JOHN V. COATS, Saratoga Springs, N. Y. This spring actuated shutter can be regulated for time and instantaneous exposures. The winding mechanism is so controlled that the spring will be equal in action at all times and at no time fully exhausted. The camera-shutter is turned by the spring. Check-arms are carried by a trip-lever for engaging and stopping the shutter at the proper point in its revolution and for releasing the shutter.

MACHINE FOR MAKING SHOVEL-HANDLES.—AUGUSTUS R. FEISTEL, Philipsburg, Penn. This invention is a machine for cutting the D-holes in the blanks of shovel and fork handles. A handle-blank is clamped in a vertically tiltable holder pivoted in a horizontally-slidable carrier, by which it is fed to a rotatable cutter-head. The holder is tilted in vertical position while the cutter is forming the D-hole and is thrown back to a horizontal position as the carriage recedes. The blank is then reversed in the holder and the operation is repeated. The inventor assures us that a machine has been constructed and is now in successful operation.

DRAG-SAW.—JAMES H. PERKINS, Seattle, Wash. A very compact and serviceable machine is provided by the present invention. All the parts are carried snugly on the bed or framing in position to be easily reached for operation. On a framing a bracket is mounted to move, carrying a wrist-pin to which a connecting-rod is attached as well as a saw-beam. A tower is mounted on the frame. In the tower a movable sling is carried, which sustains the free end of the saw-beam. The sling is moved by winding devices at the top of the tower.

Railway Appliances.

VEGETATION-BURNER FOR RAILROAD-TRACKS.—CORNELIUS BURKE and JOHN TOOLE, Monroe, La. The invention provides a new and improved vegetation-burner for railroad-tracks, which burner is especially designed for use on a push or flat car. On a truck, levers are fulcrumed, extending rearwardly beyond the truck. These levers are provided with nuts between their ends, which nuts engage screw-rods on the truck. The outer ends of the levers carry a tube from which burner-pipes depend. A transverse sheet of flame is produced, which can be raised or lowered so that high or low weeds or grass can be readily destroyed.

Miscellaneous Inventions.

SAD-IRON.—IVER WICKLAND, South Superior, Wis. The sad-iron is heated by gas or vapor supplied from oil in a tank carried by the sad-iron. A box is fitted in the front portion of the sad-iron body and forms an oil-cup, the box being in communication with the oil-supply. A retort communicates with the box and a burner is situated rearwardly of the box.

BRIDLE BLIND.—FRANK MACK, Manhattan, New York city. Mr. Mack has devised blinkers or blinders which can be made completely to blind a horse and thereby to stop him. Each blinker comprises a pivotally-mounted shade movable on its pivot to cover or uncover the eyes of the horse, and a wheel with two cams to actuate the shade.

FOLDING FLASH-LIGHT BRACKET. — OTTO C. BOTZ, Sedalia, Mo. The bracket has a supporting-bar for attachment to a socket in the camera. An extension-rod is fulcrumed on the supporting-bar. Pivotally connected with the extension-rod is an extension-upright consisting of telescopic sections for carrying the flash-light material. A spring holds the sections as adjusted.

MAIL-BOX.—WILLIAM J. WEAVER, Leetonia, Ohio. This invention relates to mail boxes particularly adapted for use on railroad mail-routes. The box is of simple construction and may be opened by a man riding on a horse or sitting in a carriage. A signal is provided for the box, which signal indicates whether the box contains mail for collecrion.

BRUSH. — MAURICE ROSENTHAL, Manhattan, New York city. Paint, varnish and calcimining brushes require bridling to enable the bristles to be properly controlled. This is generally done by tying a string around the bristles just below the ferrule. Brushes are best when the bristles are long, thus giving elasticity, or, as painters call it, "life," to the brush. The inventor attains these ends by fastening a flexible center-piece to the brush within the mass of bristles and tying the bristles snugly around the center-piece.

BEDSTEAD FASTENING. — FRED C. F. PETERS, Monroe, La. The purpose of the invention is to provide a bedstead-fastening which will securely bind the parts of a bed together and prevent them from becoming detached by breakage or movement. The fastening comprises two sections, the first of which has a flat outstanding part and the second of which has two flat outstanding parts lying in parallel planes and receiving the outstanding part of the first section between them. A pin is carried by the first section and is disposed transversely to the corresponding outstanding part. The second section has a recess in one of its outstanding parts to receive the pin.

FITTING.—JOHN R. MOODY, Perry, Iowa. The fitting is designed for repairing broken pipes, and for connecting pipes with one another, with elbows, reducers, tees, valves, without the necessity of threading the pipe or the device with which the pipe is connected. The pipe-fitting has external threads and is adapted to receive the ends of a pipe. A collar is fitted on the pipe end, is removably secured, but is held against longitudinal movement. The collar abuts on the end of the fitting. A coupling is slipped over the pipe and screws on the threads of the fitting. A packing in the coupling is adapted to be compressed against the collar.

WASHBOILER. — HIRAM H. TUTTLE, 1210 Vine Street, Philadelphia, Penn. When heat is applied to the boiler, the water begins to boil; and a circulation is established downward along the sides and ends of the boiler. The water is forced up through lines of tubes from the bottom with a direct force and discharged by such direct force below the clothing to be washed. The clothing is thereby opened up and subjected to the action of the circulating water.

STAGE-ILLUSION APPARATUS. — MORGAN A. SHERWOOD, National Theater, Washington, D. C. The invention provides an apparatus for producing a scenic representation of the burning of a person at the stake, with wonderfully realistic and startling effect, and also means for producing fire and flame effects in connection with representation in general.

METALLIC PACKING.—WILLIAM H. PRENDERGAST, Savannah, Ga. The packing is designed to be used on piston-rods and in air-pumps and is composed of packing ring sections over which lies an equalizing plate having pocket-like seats at its ends. A spring fits over the equalizing-plate and is engaged at its ends.

MOTOR-VEHICLE.—AVON M. COBURN, Daunt, Cal. The inventor mounts his engine horizontally and causes it to drive a power-shaft journaled in the middle of the vehicle below the seat. The power is transmitted by a friction-pulley to an intermediate shaft and then by sprocket and chain to the rear axle. By this arrangement power is transmitted without jerk or jar to the driving-wheel.

Designs.

BARREL. — GORDON D. CANFIELD, Washington, N. C. The barrel has a central row of diamond-shaped openings which alternate in the direction of length of the barrel with tapered openings lying nearer the ends of the barrel and giving the latter a novel appearance.

NOTE.—Copies of any of these patents can be furnished by Munn & Co. for ten cents each. Please state the name of the patentee, title of the invention, and date of this paper.

NEW BOOKS, ETC.

MOTOR VEHICLES AND MOTORS: THEIR DESIGN, CONSTRUCTION AND WORKING BY STEAM, OIL AND ELECTRICITY. By W. Worley Beaumont. London: Archibald Constable & Company. Philadelphia: J. B. Lippincott Company. 1900. 4to. Pp. 636. Price $10.

Mr. Beaumont has the unique distinction of furnishing to the automobile world the most important contribution ever made to the subject. We cannot speak in too high terms of the style in which the work is gotten up; it is splendidly printed, with rubricated paragraph indexes on the margin. The illustrations, which number 450, are well executed and are on a liberal scale, there being many folding plates. On the whole the book may be regarded as a model piece of technical bookmaking. The subject is treated in a remarkably thorough manner, and no phase of it seems to have been neglected. About the only criticism which can be made is that American practice is not as well represented as it should be. It is an indispensable book for every constructing engineer.

Business and Personal.

Marine Iron Works. Chicago. Catalogue free.

For mining engines. J. S. Mundy, Newark, N. J.

"U. S." Metal Polish. Indianapolis. Samples free.

Yankee Notions. Waterbury Button Co., Waterb'y, Ct.

Handle & Spoke Mchy. Ober Mfg. Co., 10 Bell St., Chagrin Falls, O.

Book "Dies and Diemaking," $1, postpaid. J. L. Lucas, Bridgeport, Ct. Send for index sheet.

Special and Automatic Machines built to drawings on contract. The Garvin Machine Co., 141 Varick St., N. Y.

The celebrated "Hornsby-Akroyd" Patent Safety Oil Engine is built by the De La Vergne Refrigerating Machine Company. Foot of East 138th Street, New York.

The best book for electricians and beginners in electricity is "Experimental Science," by Geo. M. Hopkins. By mail, $4. Munn & Co., publishers, 361 Broadway, N. Y.

☞ Send for new and complete catalogue of Scientific and other Books for sale by Munn & Co., 361 Broadway, New York. Free on application.

Notes & Queries

HINTS TO CORRESPONDENTS.

Names and Address must accompany all letters or no attention will be paid thereto. This is for our information and not for publication.

References to former articles or answers should give date of paper and page or number of question.

Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and, though we endeavor to reply to all either by letter or in this department, each must take his turn.

Buyers wishing to purchase any article not advertised in our columns will be furnished with addresses of houses manufacturing or carrying the same.

Special Written Information on matters of personal rather than general interest cannot be expected without remuneration.

Scientific American Supplements referred to may be had at the office. Price 10 cents each.

Books referred to promptly supplied on receipt of price.

Minerals sent for examination should be distinctly marked or labeled.

(7993) J. G. B. writes: Will you please tell me through the columns of your paper if the mouth of the Mississippi River is higher than its head waters? Has the subject ever been discussed by the North American Geographical Society? A. The mouth of the Mississippi River is several miles further from the center of the earth than its source is. This is due to the form of the earth, which has been affected by the centrifugal force of its rotation upon its axis. In this sense the mouth of any river which flows toward the south is higher than its source. It is not true in any proper sense of the term that the water of such a river flows up hill. It should not be thought, however, that this affects a water level. This is affected in the same way as the flowing river. The surface of the ocean is a water level from the equator to the poles. We do not know that any society has discussed this question.

INDEX OF INVENTIONS

For which Letters Patent of the United States were Issued for the Week Ending

NOVEMBER 20, 1900,

AND EACH BEARING THAT DATE.

[See note at end of list about copies of these patents.]

Acetone compound of nitro-meta-toluylic aldehyde, J. Koetschet ... 662,076
Advertising cover for baskets, etc., A. C. Simkins ... 662,204
Air, apparatus for removing moisture from, E. S. Belden ... 661,944
Air brake, Omick & Magann ... 662,152
Air brakes in emergencies, means for applying automatic, J. F. Hutchisson ... 662,360
Air engine, compressed, M. Flood ... 662,189
Air vent, A. Roesch ... 662,093
Amalgamating apparatus, T. R. Jordan ... 661,995
Animal trap, J. B. Lindsey ... 662,279
Armature core space block, Mix & Faure ... 662,010
Aural battery, C. W. Levalley ... 662,278
Autographic register, Dinkelbihler & Crane ... 661,961
Automobile, D. L. Sauerbering ... 662,090
Automobile starting mechanism, J. G. MacPherson ... 662,007
Baler, hay, J. Ross ... 662,028
Barber pole, C. R. Hanson ... 661,979
Bath cabinet frame, O. C. Daugherty ... 662,145
Battery plate separator, secondary, H. Leitner ... 662,277
Beam hanger, G. E. Escher ... 662,228
Beam supporter, L. Berry ... 661,946
Bearing, antifriction, T. B. Dooley ... 662,373, 662,374
Bed bottom, spring, S. D. Dilts ... 661,959
Bed, folding, J. F. Wilmot ... 662,213
Beverages, producing dealcoholized fermented, A. Muller ... 662,172
Bicycle, F. J. Gibbs ... 661,973
Bicycle frame, J. S. Dikeman ... 662,115
Bicycle saddle, B. F. Wheeler ... 662,158
Biscuit making machine, G. S. Baker ... 662,336
Boat, serpentine, J. Gresham ... 662,067
Boiler flues, apparatus for manufacturing flanged, F. L. Lane ... 662,125 to 662,127
Boiler incrustations, compound for preventing, J. Smit ... 662,205
Book, manifold sales, F. M. Turck ... 662,043
Boot cleaner, G. L. Lamb ... 662,237
Boot or shoe welt, W. A. Knipe ... 662,378
Bottle, C. F. Kihn ... 662,149
Bottle, S. F. O'Leary ... 662,088
Bottle case or cover, C. Degemeyer, Jr ... 662,257
Bottle filling machine, Nichols & Fowler ... 662,087
Bottle filling machine bottle support, Nichols & Fowler ... 662,086
Bottle, non-refillable, S. Bookheim ... 661,948
Bottle, non-refillable, W. H. Ferris ... 662,065
Box fastener, M. C. Ryan ... 662,311
Box nailing device, I. E. Davis ... 661,957
Box or vessel for powdered or granular material, E. E. Clement ... 662,353
Bread making machine, automatic, C. Kessler ... 661,999
Brick G. E. A. Holdsworth ... 662,119
Brick or block for metallurgical furnaces and preparing same, lining, E. F. McDowell ... 662,288
Brooder, chicken, Brown & Sturtevant ... 662,347
Buckle, lock, C. A. Goozey ... 661,974
Burning liquid fuel, apparatus for, J. Smith ... 662,319
Button, E. S. Smith ... 662,033
Caisson, W. H. McFadden (reissue) ... 11,873
Calorimeter, R. C. Carpenter ... 662,143
Cameras, reversible back for, A. D. Davis ... 661,956
Cane and umbrella, combined, E. Hugendubel ... 661,990
Cap vizor, M. Mattes ... 662,282
Car coupling, O. Cauvin ... 662,351
Car coupling, J. H. Hopkins ... 662,359
Car loading apparatus, A. Streily ... 662,037
Car motors and brakes, controller for electric, A. Grossman ... 662,358
Car side bearing, railway, R. Harding ... 661,981
Car sign, electric, I. B. Brower ... 662,218
Cars, mechanism for raising or lowering footboards on open, R. E. Lintner ... 662,006
Carbons for electrical purposes, manufactnring, E. Pohl ... 662,090
Carbureter, H. Burton ... 662,349
Carbureter, G. L. Reenstierna ... 662,304
Carbureter, V. J. A. Rey ... 662,024
Carriage boot, E. R. Briggs ... 662,183
Carriage leaf spring, D. N. Kratzer ... 662,124
Cartridge, combination gun, H. A. Tellerson ... 662,137
Caster, furniture, A. B. Clark ... 662,113
Centrifugal machine, continuous, W. A. Wood ... 662,214
Chain, lady's guard, S. Lederer ... 662,171
Chlormethyl salicylate of thymol, A. Eichengrun ... 662,116
Churn, S. A. Mitchel ... 662,129
Cigar perforator, D. C. Carr ... 661,951
Cigar pouch, J. J. Dittgen ... 662,226
Cigarette machine, H. Robinson ... 662,027
Circuit breaking apparatus, automatic, G. T. Woods ... 662,049
Circuit closing device, E. W. Hazazer ... 662,234
Clipper, A. Quarrie ... 662,302
Clod crusher and land leveler, Blaine & South ... 662,370
Clod crusher and sod cutter, S. T. Payne ... 662,366
Clothes line reel, H. Cook ... 662,222
Clutch for wire drawing machinery, J. W. Hawkins ... 662,270
Coffee mill, S. A. Mitchell ... 662,128
Coffee roasting apparatus, J. R. Okell ... 662,294
Comb, I. & J. Rheinberg ... 662,305
Combination lock, Morse & Bemis ... 662,285
Compasses, R. L. Nye ... 662,281
Concentrating apparatus, T. R. Jordan ... 661,997
Concentrating minerals, etc., apparatus for, T. R. Jordan ... 661,994
Controller, E. W. Stull ... 662,038
Copper weldable, rendering, C. L. Leiby ... 662,251
Copy holder, J. W. Harsha ... 662,193
Core, collapsible, G. H. Ricke ... 662,091
Core oven, T. I. Rankin ... 662,303
Corn crusher and fodder shredder, combined, V. Fuhr ... 661,969
Corn shelling machine feed attachment, D. Wandscheer ... 662,105
Corset, K. M. C. Meredith ... 662,283
Cotton cleaner and boll huller, R. R. Boyd ... 661,949
Cotton press, W. A. Patterson ... 662,299
Cover for shipping or storage vessels, ventilating, F. C. Oltrogge ... 662,295
Cow tail holder, J. E. Weldon ... 662,044
Crank hanger, W. H. Fauber ... 662,230
Crate, egg, Palmer & Lake ... 662,018
Cream separator, Titus & Battey ... 662,325
Crushing machine, T. R. Jordan ... 661,993, 661,998
Cuff holder, J. G. Kirchhofer ... 662,197
Cuff holder, E. C. Shedd ... 662,314
Cultivator coupling, G. T. Crobarger ... 662,058
Cultivator, disk, L. Kirlin ... 662,275
Cultivator, riding sulky, J. Jelen ... 662,194
Cultivator, walking sulky, J. Jelen ... 662,195
Curtain pole support and shade roller bracket, combined, H. M. Benson ... 662,053
Cutter body and making same, E. Childs ... 662,352
Cutting machine, D. Carlaw ... 662,186
Cycle saddle attachment, Brooks and Holt ... 662,346
Damping pad, etc., Weaver & Baddeley ... 662,328
Dental handpiece, H. F. Jones ... 662,070
Desk and seat, combined school, G. P. Benton ... 662,182
Display device, J. A. Pettey ... 662,098
Door lock, open, H. J. Perkins ... 662,300
Draft equalizer, H. Kugler ... 662,198
Draft evener, J. Branning ... 662,164
Dredger, S. A. West ... 662,329
Dredging apparatus, M. M. J. O. O'Conor ... 662,293
Dredging apparatus, H. R. Wheeler ... 662,219
Dressing chair, C. A. Robertson ... 662,025
Drum, heating, J. Mahedy ... 662,364
Dye and making same, blue-red azo, Israel & Kothe ... 662,122
Dye and making same, gallocyanin sulfite, C. De la Harpe et al ... 662,224
Dye and making same, indigo, J. Koetschet ... 662,073
Dyeing, E. Haussmann ... 661,985
Dyeing apparatus, W. Mather ... 662,281
Electric fixtures, supporting block or bracket for, J. W. Heizer ... 661,986
Electric machine, dynamo, F. W. Throop ... 662,042
Electric motor control, F. W. Garrett ... 661,971
Electric motor control, E. W. Stull ... 662,039
Electric motor controller, F. W. Garrett ... 661,972
Electrolytic apparatus, E. Motz ... 662,286
Elevator door, E. Rubbert ... 662,095
Elevator safety appliance, Gracey & Gfeller ... 662,264
Engine dash pot, steam, M. R. Moore ... 662,011
Engine operated by fluid under pressure, G. Geuder ... 662,169
Engine stopping device, M. J. Carroll et al ... 662,144
Engines, electric ignition plug for internal-combustion, F. R. Simms ... 662,317
Engines, sparking igniter for explosive, A. J. Signor ... 662,315
Exercising and massage device, B. A. McFadden ... 662,083
Expansible bit, J. P. Lavigne ... 662,199
Explosion engine, T. L. & T. J. Sturtevant ... 662,040
Explosive engine, multiple-cylinder, A. J. Signor ... 662,155
Extension table, Nonnast & Tesar ... 662,290
Extension table, roller top, C. D. & J. P. Barr ... 662,109
Fabric strength testing device, W. M. Vermilye ... 662,327
Faucet, water, J. P. Farley ... 661,966
Fertilizer feeding and disintegrating apparatus, J. F. Bussels ... 662,350
Filler tip, F. L. Nichols ... 662,085
Filtering apparatus, I. O. Crosscup ... 662,252
Filtering or purifying and aerating water, apparatus for, J. A. Wiedersheim ... 662,211
Fire alarm device, automatic, E. F. Sitts ... 662,032
Fire escape, O. Nelson ... 662,243
Fire escape, C. Stoll ... 662,036
Fire pump apparatus for buildings, J. Ewart ... 662,229
Fired or burned, apparatus for supporting and carrying into or withdrawing from ovens articles to be, E. W. Ball et al ... 662,161
Fireproof construction, C. A. Balph ... 662,162
Fishing bait, artificial, E. A. Warren ... 662,139
Floating body, E. G. Bailey ... 662,335
Floor, E. Goebst ... 662,376
Flue stopper, J. L. Clark ... 662,220
Fluid pressure motor, double acting, W. Chilton ... 662,056
Friction brake, J. H. K. McCollum ... 662,012
Furnace, Koehler & Calmbach ... 662,072
Furnace air heating protector, Abbs & Glynn ... 662,107
Furnaces, pneumatic device applicable to rivet heating, B. A. Brown ... 661,950
Furrow opener, marker, and coverer, combined, A. Glitz ... 662,192
Game apparatus, I. O. Nissley ... 662,151
Game registering device, pool, W. Taber ... 662,322
Garment hanger, accessible, S. W. Bonsall ... 661,947
Gas burner, C. S. Steward ... 662,035
Gas burner, incandescent, A. P. Storrs ... 662,321
Gas burner, incandescent, C. W. Taylor ... 662,323, 662,324
Gas burners, automatic shut-off and alarm for, J. G. McAlpine, Jr ... 662,082
Gas engine, Altham & Beattie ... 662,181
Gas generating machine, J. F. Kistler ... 662,276
Gas lights, mantle and mantle support for incandescent, M. & A. T. Herskovitz ... 662,381
Gas producers, steam superheater for, E. J. Duff ... 662,062
Gas, storing acetylene, E. N. Dickerson ... 662,258
Gases, means for conserving liquid, J. F. Brady ... 662,217
Gear blank, Boyd & West ... 662,344
Glass articles, apparatus for manufacturing hollow, P. T. Sievert ... 662,203
Golf tee, H. E. Wetzel ... 662,268
Governor, engine, E. Irwin ... 662,121
Governor, pressure, A. Roesch ... 662,094
Grain binder, W. C. Martin ... 662,079
Grate, dumping, E. Gibson ... 662,118
Grinding wheel center, J. Macphail ... 662,239, 662,240
Guns, firing mechanism for automatic quick-firing, Dawson & Silverman ... 662,256
Hackling machine, J. V. Eves ... 662,117
Hanger. See Beam hanger. Crank hanger.
Harness pad former, J. A. Kramer ... 662,123
Harvester, corn, A. N. Russell ... 662,309
Hat brim rounding machine, J. Stewart, Jr ... 662,176
Hatchway cover fastening, M. Mulholland ... 662,130
Hatter's tank strainer, Dwyer & Whittaker ... 662,259
Hay press, A. Bennett ... 662,341
Hay press, A. Sherrer ... 662,100
Heater and stock tank, combined, Schoenwetter & Schultz ... 662,098
Heaters, automatic temperature regulator for water, A. Roesch ... 662,092
Heating and ventilating system, I. D. Smead ... 662,103
Hinge safety guard, J. H. Pineo ... 662,201
Hose and weeder, combined, G. A. Morrell ... 662,284
Hoist, cannery, J. C. West ... 662,157
Hoisting apparatus, H. C. Behr ... 662,163
Horse controlling device, C. E. Willis ... 662,331
Hose coupling, C. Diehl ... 662,225
Hose reel, E. Cliff ... 661,953
Hydrosulfite and making same, double, M. Bazlen ... 662,338, 662,339
Incandescent mantle, A. Koch ... 662,170
Insect guard, R. Forrest ... 662,261
Ironing table, S. D. Dilts ... 661,960
Jar closure, J. C. Mills ... 662,241
Knitting machines, presser for spring needle, F. Hammond ... 662,268
Knitting or like machines, driving means for, F. Wilcomb ... 662,159
Ladder, I. M. Dillman ... 662,060
Ladder, store, E. W. Balfour ... 662,108
Lamp, M. & V. B. Cahill ... 662,165
Lamp, electric arc, J. J. Wood ... 662,048
Lamp ventilator cap, street, A. E. Shaw ... 662,313
Lamps, terminal connection for electric, A. J. Wurts ... 662,369
Lathe screw cutting attachment, J. Cornelis ... 662,188
Lathe, turning, F. R. Clark ... 662,371
Lever locking mechanism, T. Coldwell ... 662,354
Linotype machine, F. J. Wich ... 662,106
Liquid separator, centrifugal, F. J. Arend ... 661,943
Locomotive boiler, J. T. Connelly ... 662,250
Locomotive turn table, L. H. Shoemaker ... 662,031
Loom, E. S. & W. I. Stimpson ... 662,320
Loom beam attachment, C. R. Saatweber ... 662,029
Magneto-electric machine, Simms & Bosch ... 662,316
Match machines, composition applying mechanism for, W. N. Palmer ... 662,297
Measuring can, oil or gasolene, F. B. Hinkelbein ... 662,273
Measuring textiles and recording scales, etc., apparatus for, E. Sauermilch ... 662,153
Mechanical movement, P. Duchscher ... 662,061
Medicinal boot or shoe, H. F. Crawford ... 662,223
Melting furnace, A. Piat ... 662,019
Memorandum blanks or the like, holder for, H. Hake ... 661,977
Moistening stamps, envelops, etc., utensil for, C. L. Jenne ... 662,196
Mold, C. F. Haglin ... 662,266
Mortar mixing machine, D. W. McGrath ... 662,173
Motor. See Fluid pressure motor.
Mowing or grain cutting machine, J. McGough ... 662,084
Music leaf turner support, S. W. Hornbeck ... 662,235
Mustache guard, D. B. Hubbard ... 662,120
Needle holder, C. Truax ... 662,178
Nitro toluylic aldehyde, J. Koetschet ... 662,074, 662,075
Nut lock, M. M. Bosworth ... 662,343
Nut lock, W. N. Keen ... 662,274
Nut lock, R. M. Reade ... 662,023
Oar and rowlock connection, A. H. Eldredge ... 662,227
Oil cup, M. J. Zahniser ... 662,051
Oven, J. L. Starks ... 662,175
Oven, bake, W. Clauss ... 662,221
Packing bag, J. Kinstler ... 662,000
Packing case, E. A. Galbraith ... 662,190
Paper bag holder, A. E. Brunson ... 662,112
Paper drying apparatus, S. A. Copenhafer ... 662,187
Paper making machines, wire web guide for, T. Harvey, Jr ... 661,982
Pen, fountain, H. Grass ... 662,357
Pencil point protector and sharpener, combination, W. L. Cranstone ... 661,955
Petroleum and compressed air burner, Charon & Manaut ... 662,055
Phonograph records, machine for reproducing, A. N. Petit ... 662,301
Photograph, colored, P. M. C. Grenier ... 661,976
Photographic finder, Magagnc & Fulton ... 662,363
Photographic plate rack, Crissy & Dulles ... 662,167
Picture support, J. Babst ... 662,140
Pipe hook, J. W. Berry ... 662,342
Planter and fertilizer distributer, combined, S. D. Roop ... 662,135
Planter, check row corn, J. C. Stanley ... 662,174
Plow, Noble & Keeton ... 662,131
Plow attachment, E. H. Kuhl ... 662,002
Plow, cultivating, C. L. Murphree ... 662,081
Pole for telegraphers, etc., E. W. Serrell ... 662,312
Pole top, P. G. Reynolds ... 662,244
Power, means for transmitting, W. Lay ... 662,077
Power transmitter, F. S. Weatherly ... 662,179
Power transmitting device, A. L. Riker ... 662,306
Press for embossing, etc., C. Seybold ... 662,099
Printer's rule, C. C. Marder ... 662,365
Printing press gage, G. C. Wolven ... 662,047
Pruning implement, R. Albach ... 662,052
Pulley, J. Winter ... 662,046
Pulley, conveyer, M. Garland ... 661,970
Pulp wood chipper, A. O. Lombard ... 662,238
Pump, W. Wildman ... 662,180
Punching bag support, Whitely & Duncan ... 662,045
Railway switch, H. O'Shea ... 662,016
Range finder and turret, combined, B. A. Fiske ... 661,968
Ratchet for pulleys, etc., roller, G. E. Hall ... 661,978
Recording instrument, message, J. J. Ruddick ... 662,308
Rifle, C. J. & C. Hamilton ... 662,068
Rifle, repeating air, W. J. Burrow ... 662,054
Rocker fan attachment, J. J. Myers ... 662,242
Rolling mechanism, L. D. Davis ... 662,146
Rolling mill tranfer table, Bryson & Evarts ... 662,348
Safe, J. H. Howard ... 661,989
Sampling, averaging, mixing, and storing materials in bulk, T. A. Edison ... 662,063
Sash holder and fastener, W. A. Hulme ... 661,991
Sashes, securing flexible material to window, O. M. Edwards ... 661,963
Saw guide, band, A. Cunningham ... 662,254
Scale beam, C. G. Strubler ... 662,367
Scale, computing, J. H. Schneider ... 662,097
Scales, dead rail stand for track, J. A. Rishel ... 662,245
Screening apparatus, T. R. Jordan ... 661,996
Screw, F. W. Rodd ... 662,134
Screw machines, etc., tool turret for, F. E. Wells ... 662,209
Sealing device, bottle, H. T. Gay ... 662,263
Seed delinting machine, cotton, H. Barditzky ... 662,337
Sewing machine darning attachment, W. Ragen ... 662,202
Sewing machine needle, S. S. Roszell ... 662,307
Shade roller, spring, E. F. Hartshorn ... 662,148
Shafting, geared flexible, E. B. Collins ... 661,954
Shears, H. A. Decker ... 661,958
Shelf protection, W. H. McNamara ... 662,014
Shingle, metallic, C. A. Galvin ... 662,262
Ships, means for controlling water ballast in, G. B. Willcox ... 662,330
Shoe trimming machine, O. A. Davis ... 662,355
Sifter, C. S. Broadman ... 662,111
Sifter, ash, S. C. Hart ... 662,269
Skirt protector, S. B. Sowden ... 662,246
Sluice gate, Prescott & Furber ... 662,022
Smoke consuming furnace, J. Slater ... 662,102
Smokehouse, Simpson & Senior ... 662,318
Snow melter, J. Mandrey ... 662,280
Soap, G. A. Schmidt ... 662,096
Soap press, E. J. Forrester ... 662,356
Spark arrester, E. Cory ... 662,114
Speed changing mechanism, Fischer & Otto ... 661,967
Speed mechanism, varying, H. B. Mitchell ... 662,380
Spraying device, liquid, J. P. Johnston ... 662,236
Stable, J. Hinks ... 661,987
Stapling machine, Ariggs & Barrett ... 662,184
Stay bolt, G. R. Joughins ... 662,071
Steam boiler, L. J. Harris ... 662,232
Steam boiler, A. Mercer ... 662,080
Steam generator, Davies & Ross ... 662,255
Steam generator, C. L. Palmer ... 662,296
Stitch machine, ornamental, I. R. Burdick ... 662,185
Stove, J. E. Hatch ... 661,984
Stove, cooking, A. S. Tompkins ... 662,326
Stovepipe, W. Haylor ... 662,233
Stovepipe collar holder, W. E. Sykes ... 662,041
Strainer, milk, E. S. Lagerquist ... 662,379
Street sweeper, W. J. Cowan ... 662,057
Sucker, Britton & Morrow ... 662,345
Sulky rake, W. Lincoln ... 662,078
Swimming device, K. F. Hoglund ... 662,069
Syringe, vaginal, J. A. Bell ... 662,340
Table tops, etc., changeable support for, Sargent & Dover ... 662,136
Tap and die, F. Ehmke ... 662,064
Tap, collapsible screw threading, S. B. Leidy ... 662,361
Tar kettle, fireproof, E. Cubbidge ... 662,253
Telegrams, means for rapidly transmitting, Pollak & Virag ... 662,020
Telegrams, rapidly transmitting, Pollak & Virag ... 662,021
Telephone receiver, H. H. Hipwell ... 661,988
Thill coupling, W. S. Castle ... 661,952
Thill coupling, J. G. Parsons ... 662,200
Thill coupling, A. H. Worrest ... 662,050
Threshing machine feed regulating mechanism, E. B. Kline ... 662,001
Throat shield, W. W. McCormick ... 662,150
Tire, W. A. Wright ... 662,332
Tire and shoe, pneumatic, A. Vreeland ... 662,208
Tire for vehicles, elastic, H. Tolman ... 662,177
Tire, non-puncturable pneumatic, E. L. & S. B. Alexander ... 662,160
Tire, non-slipping rubber, K. A. Enlind ... 661,965
Tire, vehicle, W. F. Masters ... 662,008
Tires, inner tube for pneumatic, T. R. Palmer ... 662,132
Tobacco stripping and booking machine, J. R. Williams ... 662,212
Tongue tip, A. A. Lerbakken ... 662,362
Tool, combination, J. C. Lewis ... 662,005
Torch and heater, C. L. Ge Frorer ... 662,191
Toy hoop, P. A. Smith ... 662,034
Toy moneybox, W. H. Dietz ... 662,059
Track structure, H. O'Shea ... 662,017
Translating device, F. M. Bell ... 662,110
Trolley, H. S. Goughnour ... 661,975
Trolley, F. A. Merrick ... 662,009
Truck, car, A. B. du Pont ... 661,962
Turfing implement, H. E. Lawrence ... 662,004
Typewriter, J. P. Angell ... 662,333
Typewriting machine, W. J. Barron ... 662,141, 662,142
Typewriting machine, C. L. Fenton ... 662,230
Typewriting machine, C. Gabrielson ... 662,147
Typewriting machine dog, H. Allender ... 662,215
Umbrella lock, E. L. Appleby ... 662,334
Vacuums, gaging high, J. Waring ... 662,156
Valve, A. W. Cadman ... 662,249
Valve, balanced slide, L. W. McDonald ... 662,287
Valve, compression engine, H. J. Schmick ... 662,154
Vehicle, J. A. Hamelback ... 662,267
Vehicle driving gear, motor, R. W. Elston ... 661,964
Vehicle driving mechanism, motor, J. E. Thornycroft ... 662,207
Vehicle frame, motor, F. R. Parker ... 662,298
Vehicle, motor, T. B. Dooley ... 662,372
Vehicle, motor, J. E. Thornycroft ... 662,206
Vehicle, motor, H. G. Underwood ... 662,138
Vehicles, power device for road, R. B. Robertson ... 662,026
Velocipede, F. B. Hunt ... 661,992
Vise, P. Anderson ... 661,942
Voltage controller, multiple, G. S. Dunn ... 662,375
Vulcanizer, P. Funck ... 662,231
Wagon, lumber or log, J. H. Harris ... 661,982
Washboiler, steam, J. C. Greiner ... 662,265
Washer, A. Lamm ... 662,003
Washing machine, piece, C. C. Kenyon ... 662,377
Water cooler dispensing device, F. A. Emerick ... 662,168
Water pressure regulator, O. Mueller ... 662,013
Watering apparatus, stock, J. H. Hanson ... 661,980
Weighing machine, automatic, J. W. Berry ... 661,945
Well drilling mechanism, artesian, L. J. McNutt ... 662,289
Wheelbarrow, V. A. Gates ... 662,066
Whim, J. H. O'Brien ... 662,292
Whip socket, O. Carter ... 662,219
Windmill, J. Calder ... 662,166
Windmill driving gear, L. W. Noyes ... 662,015
Wire, coated, J. H. Vinton ... 662,247
Wire drawing machine draw in, J. W. Hawkins ... 662,272
Wire drawing machines, adjustable die holder for, J. W. Hawkins ... 662,271
Wire rope sockets, making metallic, W. S. Bidle ... 662,216
Wire stretcher, B. H. Passmore ... 662,133
Wire tightener, W. A. Short ... 662,101
Wood impregnating apparatus, Stern & Kempner ... 662,104
Wood impregnating compound and making same, J. Rutgers ... 662,310

DESIGNS.

Bicycle or like tubular frames, fork for, Fauber & Price ... 33,596
Bicycle or like tubular frames, fork for, A. M. Price ... 33,597
Bracket for curtain poles and window shades, A. Anderson ... 33,588
Bread or similar article, loaf of, Freihofer & Hanson ... 33,610
Bread or similar article, loaf of, Hanson & Freihofer ... 33,609
Brick, fire, W. M. Brinkerhoff ... 33,601
Brushes, etc., back for, W. F. Marshall ... 33,575
Buckle, J. L. Poalk ... 33,577
Calendar, M. C. Hall ... 33,572
Car coupling knuckle, S. J. Meeker ... 33,591
Comb, F. W. Grell ... 33,574
Comb and pencil holder, F. J. French ... 33,573
Concentrating minerals, tube for, T. R. Jordan, 33,578, 33,579
Corset side section, E. T. Muir ... 33,606
Cycle crank hanger, motor, G. M. Holley ... 33,599
Cycle frame, motor, G. M. Holley ... 33,598
Dispensing vessel, B. F. Merssmann ... 33,582
Door hanger pulley frame, P. A. Myers ... 33,590
Engine frame, gas, G. A. Timblin ... 33,592
Eye, garment, A. M. Marshall ... 33,576
Game board, F. D. Fuller ... 33,604
Glass, sheet, W. Buttler ... 33,603
Grave headpiece, E. Bick ... 33,602
Pan cover, bake, Hanson & Freihofer ... 33,583
Ring, G. A. Henckel ... 33,607
Rug, etc., L. M. Armstrong ... 33,608
Sewing machine frame, H. J. Hancock ... 33,585
Shoe arch spring, J. Slater ... 33,605
Sprayer body, G. F. Clark ... 33,580, 33,581
Telephone case, slot, W. A. Foss ... 33,593
Telephone pole box, W. D. Gharky ... 33,594
Tool handle receptacle, E. B. Higgins ... 33,589
Towel holder, L. McCutchon ... 33,584
Vapor burner, I. N. Marquis ... 33,587
Wagon body, P. J. Reid ... 33,600
Weather vane, D. Haight ... 33,586
Wheel, sprocket, W. E. Norton ... 33,595

TRADE MARKS.

Agricultural machinery, Deering Harvester Company ... 35,488
Apparel, certain named wearing, H. Black & Company ... 35,451
Beer, National Brewery Company ... 35,466
Bottle washing machines, A. E. Rich ... 35,487
Canned fresh water fish, Buckeye Fish Company ... 35,473
Canned meats, F. Wolferman ... 35,474
Cement, Portland, Hammer Society ... 35,461
Chucks, lathe and drill, Westcott Chuck Company ... 35,486
Coats, sack, Sweet, Orr & Company ... 35,449
Coffee substitute, W. Brenow ... 35,467
Coffee substitutes, D. H. Smith ... 35,468
Corsets and bust forms, Bortree Corset Company ... 35,452
Dairy products, certain named, New York Condensed Milk Company ... 35,472
Dampers for hot air pipes and smoke pipes, S. M. Howes Company ... 35,482
Firearms, Remington Arms Company ... 35,457
Flour, wheat, Duluth Universal Mill Company ... 35,472
Gin, Tanqueray, Gordon & Company ... 35,465
Groceries, certain named, Cudahy Packing Company ... 35,476
Groceries, certain named, J. F. Humphrey & Company ... 35,477 to 35,479
Jelly, butter, cider, and boiled cider made from apples, A. A. Low ... 35,469
Leather, tanned, B. D. Eisendrath ... 35,454
Medicinal preparations, certain named, J. W. Hahn ... 35,462
Mineral waters and drinks made from same, F. F. Whittier ... 35,464
Paint composition, A. L. Rice ... 35,458
Paints and enamels, Gerstendorfer Brothers ... 35,459
Paper, carbon, Typewriter Cushion Key Company ... 35,448
Petroleum, refined, R. C. Corner ... 35,460
Pianos, O. Wissner ... 35,480
Pipes, pipe couplings, and pipe fittings, Central Foundry Company ... 35,483, 35,484
Poultry, dressed, Priebe & Simater ... 35,475
Preparations for the complexion, G. T. Brandon ... 35,463
Shirts, bed robes, and panjamas, D. Jones & Sons ... 35,450
Stoves, ranges, furnaces, and parts thereof, Pittsburg Stove and Range Company ... 35,481
Toothpicks, wooden, C. Forster ... 35,455 to 35,457
Underwear, certain named article of, H. L. Fording ... 35,453
Wine, jelly, and preserves made from wild grapes, A. A. Low ... 35,470

LABELS.

"A. B. C.," for beer, American Brewing Company, 7,909 to 7,911
"American Gentleman Rye Whisky," for whisky, A. Herzberg ... 7,914
"Armoza," for cigars, American Lithographic Company ... 7,902
"Blue Label," for whisky, A. Forbes ... 7,913
"Crystal Rock," for beer, Cleveland & Sandusky Brewing Company ... 7,912
"Dotty Dimple," for canned tomatoes, United States Printing Company ... 7,897
"Horse Radish Jack," for horse radish, A. Cliff ... 7,899
"La Introduction," for cigars, Schmidt & Company ... 7,906
"Love Knot Brand," for canned tomatoes, United States Printing Company ... 7,896
"Montana Sport," for cigars, Schmidt & Company ... 7,905
"Murillo," for cigars, Cuban American Manufacturing Company ... 7,903
"Nanine," for cigars, Schmidt & Company ... 7,904
"Oil of Vanilla," for an extract, D. Lamont ... 7,898
"Pa-kal," for a medicine, A. H. Olmstead ... 7,901
"Railway Supplies and Pulp Wood," for railway supplies, etc., L. R. Martin ... 7,916
"Sand Stone Brand," for butter, J. E. Amend ... 7,894
"Silver Creek Creamery," for butter, J. J. Powers & Company ... 7,893
"The Blue and the Gray," for beer, American Brewing Association ... 7,908
"The Famous Maryland Carpets," for carpets, J. Hines & Son ... 7,915
"The New Process Butter Company," for oleomargarin and butterin, G. D. Davis ... 7,895
"The We Girls Company Cigar," for cigars, We Girls Company ... 7,907
"Woman's Friend," for an antiseptic, Standard Remedy Company ... 7,900

PRINTS.

"La Numancia," for cigars, Schmidt & Company ... 275
"The We Girls Company," for cigars, We Girls Company ... 276

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 10 cents. In ordering please state the name and number of the patent desired, and remit to Munn & Co., 361 Broadway, New York.

Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list, provided they are simple, at a cost of $40 each. If complicated the cost will be a little more. For full instructions address Munn & Co., 361 Broadway, New York. Other foreign patents may also be obtained.



"Star" Foot and Power Screw Cutting Automatic Cross Feed **Lathes**

FOR FINE, ACCURATE WORK

Send for Catalogue B.

SENECA FALLS MFG. CO.
695 Water Street,
Seneca Falls, N.Y., U. S. A.

ENGINE & FOOT LATHES. MACHINE SHOP OUTFITS. TOOLS AND SUPPLIES. CATALOGUE FREE. SEBASTIAN LATHE CO. 120 CULVERT ST. CINCINNATI, O.

Tool Topics Tersely Treated.

There is no book in the world devoted exclusively to the description and illustration of Tools for all trades except the thoroughly up-to-date and improved edition of

MONTGOMERY & CO.'S TOOL CATALOGUE.

It is a handy book of ready information about every known tool and has a copious index for reference. Pocket size. Sent by mail for 25 cents.

MONTGOMERY & CO., 105 Fulton St., New York City.

WORK SHOPS

of Wood and Metal Workers, without steam power, equipped with

BARNES' FOOT POWER MACHINERY

allow lower bids on jobs, and give greater profit on the work. Machines sent on trial if desired. *Catalog Free.*

W. F. & JOHN BARNES CO.
1999 RUBY ST., ROCKFORD, ILL.

PHYSICAL AND SCHOOL APPARATUS



TOEPLER HOLTZ SELF CHARGING MACHINE

For School, College or X Ray work.

☞ *Circular free.*

E. S. RITCHIE & SONS,
Brookline, Mass.

THE JOHNSON ROTARY PUMP.

Simple of construction, positive in action, easy and quiet in operation. Especially adapted to pumping soap, oil, sugar, lard, glucose, acids, starch, glue, varnish, coal and water, malt, etc. Large sizes for irrigation.



Made as a belt or steam pump, or combination, or operated by electric motor or gasoline engine. Manufactured by

DAVIS-JOHNSON CO., Station V, CHICAGO, ILL.

SAVE ONE-HALF YOUR FUEL We Tell You How.

Rochester Radiator Co. 26 Furnace St. Rochester, N.Y.

CUYER'S PATENT
DESULPHURIZING FURNACE.



Latest, Cheapest and Best.
Takes the place of Heap or Stall Roasting.
Saves time and money.
Write for particulars.

HENRY GUYER, Casilia 514, LIMA, PERU, S. A.

The Perfection of Pipe Threading

is admitted to be reached when our **No. 9½ PIPE THREADING MACHINE** is used. As a hand machine it is the only one known that will cut and thread an 8 inch pipe with ease and satisfaction. One valuable feature is, that it has no arbitrary lead screw for determining style or pitch of thread to be cut. ☞ *Send for Catalogue.*



THE MERRELL MFG. CO.
501 Curtiss St., Toledo, Ohio.

PERFECT - PUMP - POWER.



is attained only in the **TABER ROTARY PUMPS**

They are mechanical, simple and durable. Will pump hot or cold fluid, thin or thick. Requires no skilled mechanic. Most power at least cost. All parts interchangeable. Made of iron, steel or bronze. Can be driven by belt, motor or engine attachment. *Large Illustrated Catalogue free.*

TABER PUMP CO., 32 Wells St., Buffalo, N.Y., U. S. A.

ZEPHYR MAGNESIA
PLASTIC COVERING.

Unequaled as a non-conductor of heat for use on all steam and fire heated surfaces.

Guaranteed to cover 40 square feet, flat surface, 1 inch thick, and weighs only 60 pounds per bag.

Magnesia Asbestos Moulded Sectional Covering,
Felted Asbestos Air Cell Sectional Covering,
Wool Felt Sectional Coverings,
Asbestos Cement, and a complete line of insulating materials of all kinds. For prices address

THE CORK FLOOR AND TILE CO.,
139 Congress Street, Boston, Mass.

Powerful, Responsive, Durable and Efficient.

"The Reeves" Variable Speed Countershaft

for securing any speed without change of belt or loss of time. Especially adapted for all kinds of Ironworking Machinery, Iron Lathes, Planers, Boring Mills, Shapers, etc.; Cement Machinery, Experimental Machinery—in fact all kinds of machinery requiring a change of speed. With it a large increase and a better grade of work can be produced.

☞ *Send for handsomely illustrated catalogue "S. A." free.*

REEVES PULLEY CO.
COLUMBUS, IND., U, S. A.

In order to introduce the new edition of **this Great Library,** the publishers have arranged with the American Newspaper Association to supply a limited number of sets to its patrons, on special terms, among which are the readers of the SCIENTIFIC AMERICAN.

Unparalleled Offer to Scientific American Readers!

THE NEW 1900 WERNER EDITION OF

Encyclopedia Britannica

Thirty-one large volumes, 8x11 inches, 25,000 pages.

WEBSTER'S ENCYCLOPEDIC DICTIONARY FREE!

WE DELIVER, FREIGHT PAID, ON RECEIPT OF $1.00

BALANCE AT THE EASY RATE OF TEN CENTS A DAY.



THE DICTIONARY is a magnificent volume of 2370 pages, over 2000 engravings, and many chromatic colored plates of great beauty.

THE NEW WERNER EDITION OF 1900

is a magnificent set of books; it is printed upon a superior quality of book paper, is strongly and elegantly bound, and above all the

Type is Large and Clear.

It is equal in EVERY respect to the English edition, of which it is a complete reprint; and in addition, our subscribers receive the **Werner Supplement,** in five volumes, which brings information to date, and is essential to American readers.

A COMPLETE FAMILY LIBRARY.

A Library of History, Biography, Law, Literature, Fine Arts, Natural Sciences, Games and Pastimes, Medicine and Hygiene, Philosophy and Psychology, Economics and Political Science, Theology and the Science of Religions.

It is a Library for the Merchant, the Student, the Young People and the Busy World.

A Library Without a Rival in Completeness, in Authority and in Up-to-date-ness.

Revised to Date.

Our Offer To Scientific American Readers

On receipt of $1.00, balance in small monthly payments of $3.00 each, we will send, freight prepaid, a complete set of

(1)—THE ENCYCLOPEDIA BRITANNICA.
(2)—THE GUIDE TO SYSTEMATIC READING.
(3)—WEBSTER'S ENCYCLOPEDIC DICTIONARY.
(4)—A SOLID OAK BOOKCASE.

SEND $1.00 TO-DAY and take advantage of this splendid opportunity, or write for full particulars, mentioning Scientific American. Money will be refunded if not satisfactory.

The American Newspaper Association
148 Fifth Avenue, New York.

HALF A BILLION
ADVANCE IN VALUES

of Stocks on the New York Stock Exchange in four days of last week following Election shows that confidence is fully restored.

Mining Stocks Lead the Boom,

and for the next few years stocks in legitimate working mines will pay the holders enormous profits if carefully selected through a responsible house. We do the largest exclusive Mining, Banking and Brokerage business in the United States, and by our thorough methods of investigation and monthly reports from our own representatives and experts in the respective camps have invariably made

PROFITS, NOT LOSSES, FOR OUR CUSTOMERS.

We have several first issues low-priced stocks and dividend payers which will pay very large and immediate profits, that any investor desiring unusual interest and absolute security of principal should investigate. Send for pamphlets of our 4 successful properties in combination and booklet, "About Ourselves," describing our successful methods and showing how the excessively large profits of mining investments can be obtained with no risk of loss.

DOUGLAS, LACEY & CO.,
Bankers & Brokers. Mining Stock Exclusively
66 Broadway—17 New St., New York.

BRANCHES:

CLEVELAND: "The Cuyahoga" Building.
PHILADELPHIA: "The Betz" Building.
BOSTON: "The International Trust Co." Building.

AMERICAN PATENTS.—AN INTERESTING and valuable table showing the number of patents granted for the various subjects upon which petitions have been filed from the beginning down to December 31, 1894. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **1002.** Price 10 cents. To be had at this office and from all newsdealers.

ALL STEEL NAIL NIPPERS.

THE RIGHT SHAPE AND MADE TO USE.

For Lifting and Cutting Ingrown or Heavy Nails, They Have No Equal.

No. 400, like cut, 4¾ Inches Long. **Price, 75 Cents,** with Leather Case.

☞ *Send for Catalogue of other Manicure Goods.*

Emil Forquignon Mfg. Co., 835 Broadway, New York.

For Sale, Machinery
Now at Norton Mills, Vermont.

IN SAW MILL AND PLANING MILL.

1 Double Engine, 200 Horse Power 3 Boilers. 1 Circular Saw Board Machine; Carriage 24 ft. 1 Circular Saw Board Machine; Carriage 55 ft. 1 Parallel Edger; Edge 40 ft. 1 Clapboard Machine. 1 Lath Machine. 1 Shingle Machine. 1 Clapboard Planer (Double); S. A. Wood's make. 2 Planers and Matchers; S. A Wood's make. 1 Edger (Light). 1 Planer (Heavy). 1 Steam Engine, 50 Horse Power. Butting, Trimming Saws, Fixtures, Shafting, Belting, etc. Apply to

STUART A. BALDWIN, Norton Mills, Vt.



ARTESIAN

Wells, Oil and Gas Wells drilled by contract to any depth from 50 to 3000 feet. We also manufacture and furnish everything required to drill and complete same. Portable Horse Power and Mounted Steam Drilling Machines for 100 to 1200 feet. Write us stating exactly what is required and send for illustrated catalogue. Address

PIERCE WELL ENGINEERING AND SUPPLY CO.
136 LIBERTY STREET, NEW YORK, U. S. A.

THE BICYCLE: ITS INFLUENCE IN Health and Disease.—By G. M. Hammond, M.D. A valuable and interesting paper in which the subject is exhaustively treated from the following standpoints: 1. The use of the cycle by persons in health. 2. The use of the cycle by persons diseased. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **1002.** Price 10 cents. To be had at this office and from all newsdealers.



Telephones,

for Interior, Short Line, Intercommunicating and Hotel Work. Write us for prices, catalogue, etc., with testimonials and references. Estimates cheerfully furnished. Agents wanted.

THE SIMPLEX INTERIOR TELEPHONE CO.,
431 Main St., Cincinnati, Ohio.



Smith Premier Typewriter
WON A DIPLOMA OF
THE GRAND PRIX, HIGHEST POSSIBLE AWARD,

—AT—

The Paris Exposition.

This award was made by an INTERNATIONAL JURY OF TWENTY-FIVE MEMBERS, AND IN COMPETITION WITH TWENTY OTHER TYPEWRITERS.

The Smith Premier Typewriter Co.,
SYRACUSE, N. Y., U. S. A.

Williams' Shaving Stick

"The Only Kind that Wont Dry on the Face"

SOLD EVERYWHERE.
Williams' Shaving Stick, 25c.
Genuine Yankee Shaving Soap, 10c.
Luxury Shaving Tablet, 25c.
Swiss Violet Shaving Cream, 50c.
Williams' Shaving Soap (Barbers'), 6 Round Cakes, 1 lb., 40c. Exquisite also for toilet. Trial cake for 2c. stamp.
The only firm in the world making a specialty of SHAVING Soaps.
THE J. B. WILLIAMS CO., Glastonbury, Ct.
LONDON PARIS DRESDEN SYDNEY

Queen Transits and Levels

High Grade Instruments with the Latest Improvements.

160 page Engineering Catalogue on application. **THE QUEEN** 240 page Mathematical Catalogue on application.

ENGINEERS' AND DRAFTSMEN'S SUPPLIES.
QUEEN & CO., Optical and Scientific Instrument Works,
59 Fifth Ave., New York. 1010 Chestnut St., Phila.

SEND 10¢ FOR 126 PAGE ILL. CATALOGUE.
GEARS AND PARTS OF MODELS
GOODNOW & WIGHTMAN. BOSTON

TO MINE OWNERS

You need a **Hoisting Engine.** You want the best, strongest, safest, most up-to-date engine that is made—the most durable and yet the greatest saver of money. Send for our free catalogue and state the size of engine you want. We build them for mines, quarries and docks. Both friction and geared hoist, 6 to 150 H. P. All parts easily interchangeable.



WEBER GAS & GASOLINE ENGINE CO., P. O. Box 1114-a, Kansas City, Mo



THE MIETZ & WEISS KEROSENE and GAS Engine

burns **KEROSENE** cheaper and safer than gasoline. Automatic, simple, reliable **No** electric battery or flame used Perfect regulation. Belted or directly coupled to dynamo for electric lighting, charging storage batteries **and all power purposes.**

☞ Send for Catalogue.

A. MIETZ,
128-138 MOTT ST., NEW YORK.
Markt & Co., London, Hamburg, Paris

HIGHEST EFFICIENCY attained in the **STOVER GASOLINE ENGINE**



The best is always cheapest. *Write for prices.*

STOVER ENGINE WORKS, FREEPORT, ILL.

PALMER Stationary and Marine Gasoline Engines and Launches, Motor Wagon Engines, Pumping Engines.

☞ Send for Catalog.

PALMER BROS., - - MIANUS, CONN.

The "Wolverine" Three Cylinder Gasoline Marine Engine.

Write for catalogue.



The only reversing and self-starting gasoline engine on the market. Lightest engine for the power built. Practically no vibration. Absolutely safe. Single, double and triple marine and stationary motors from ¾ to 30 H. P.

WOLVERINE MOTOR WORKS,
Grand Rapids, Mich.



"NEW YANKEE" DRILL GRINDER.

A MECHANICAL TRIUMPH.

50% of time saved. No calipers, gauges or measuring instruments. Any clearance obtained instantly. Simplest machine ever invented.

Send for catalogue of 10 styles.

WILMARTH & MORMAN CO.,
153 Canal St., Grand Rapids, Mich., U.S.A.

MILLS FOR ALL MATERIALS.



OUR BUSINESS IS TO MAKE MACHINERY FOR GRINDING GRAIN, CRUSHING ROCKS AND PULVERIZING ALL HARD SUBSTANCES. WE HANDLE ALL KINDS OF MATERIALS FROM COTTON-SEED TO ROOTS AND HERBS, BY AN UNEXCELLED PROCESS. IF YOU WANT ANY KIND OF A MILL OR GRINDING MACHINE, COME TO US AND YOU WILL GET THE BEST AND STILL SAVE MONEY.

DEAL WITH US ONCE AND YOU WONT CHANGE.
ESTIMATES FREELY FURNISHED.
SPROUT, WALDRON & CO.
SEND FOR CATALOG No 4. MUNCY, PA.

Send your business card for 16 p. illus. catalogue.



NICKEL
AND
Electro-Plating
Apparatus and Material.
THE
Hanson & VanWinkle Co.,
Newark, N. J.
136 Liberty St., N. Y.
30 & 32 S. Canal St Chicago.

RESTFUL SLEEP
In Camp, on the Yacht and at Home.
"Perfection" Air Mattresses,
CUSHIONS and PILLOWS.

Style 61. Camp Mattress with Pillow attached. Also showing Mattress deflated.

Clean and Odorless, will not absorb moisture.
Can be packed in small space when not in use.
☞ *Send for Illustrated Catalogue.*
MECHANICAL FABRIC CO., PROVIDENCE, R. I.

Porter's Humane Bridle.
No Bit in the Horse's Mouth.

Horsemen indorse this Bridle because it is the best for all horses. It prevents frothing, lolling of the tongue, etc. No more trouble with sore mouths. The hardest pullers driven with ease. Every lover of the horse should use it, because it is humane. **Equipped with Straps to Fit Any Bridle.**

Retail Best Grade Nickel, - **$5.00**
Retail Best Grade Enamel, **4.00**
Second Grade Nickel, - - - **3.50**
Second Grade Enamel, - - **3.00**

If your hardware or harness dealers do not have them write us.
Sent prepaid on receipt of retail price.
State if you use side-check or overdraw. Agents Wanted.
PORTER HUMANE BRIDLE CO.,
Dept. A, Sudbury Building, Boston, Mass.

CROOKES TUBES AND ROENTGEN'S Photography.—The new photography as performed by the use of Crookes tubes as a source of excitation. All about Crookes tubes. SCIENTIFIC AMERICAN SUPPLEMENT, Nos. **181, 189, 238, 243, 244, 792, 795 905, 908, 1050, 1054, 1055, 1056, 1057.** also SCIENTIFIC AMERICAN, Nos. **7, 8, 10** and **14.** Vol. 74. These profusely illustrated SUPPLEMENTS contain a most exhaustive series of articles on Crookes tubes and the experiments performed with them. Among them will be found Prof. Crookes' early lectures, detailing very fully the experiments which so excited the world, and which are now again exciting attention in connection with Roentgen's photography. Price 10 cents each To be had at this office and from all newsdealers.

SENT ON TRIAL.
Prepaid to any address.



Coggeshall Patent Steam Tube Cleaner.
THE CLEANER THAT CLEANS CLEAN
NO Moisture, Saves cost quickly. **A trial costs**
Scale. Cleans from end to end. **you nothing**
The Coggeshall Mfg. Co., 123 Liberty St., New York.

Acetylene Gas Lighting
Reduced to the most Efficient, Safest, Simple and Economical Use.



We guarantee our machines perfectly automatic in action, to extract all the gas from the carbide, and absolutely no over production or loss of gas. Approved by the various Boards of Fire Underwriters. Standard sizes 10 to 150 lights. Exclusive territory given to responsible agents. Correspond with
NIAGARA FALLS ACETYLENE GAS MACHINE CO.,
Niagara Falls, N. Y. and Canada.

WE ARE SELLING

Battery Hanging Lamps	$10.00
Telephone, complete, -	5.95
Electric Door Bells, - -	1.00
Electric Carriage Lights,	5.00
Battery Fan Motor, - -	5.95
Electric Hand Lanterns,	2.00
Pocket Flash Lights, -	1.50
Miniature Electric Lamps,	.40
$8 Medical Batteries, -	3.95
Genuine Electric Belts,	1.00
$12 Belt with Suspensory,	2.50
Genuine Electric Insoles,	.25
Telegraph Outfits, - -	2.75
Battery Motors from $1 to	12.00
Battery Table Lamps, -	3.00
Necktie Lights, 75 cts. to	3.00
Bicycle Electric Lights,	2.25
Electric Cap Lights, -	2.00
Electric Railway, - -	3.50
Battery Student Lamp, -	4.00
Dry Batteries, per dozen,	2.25

Electric Books at low prices.
We undersell all on Everything Electrical.
OHIO ELECTRIC WORKS
CLEVELAND, O.
Headquarters for Electric Novelties and Supplies.
Agents wanted. Send for New Catalogue, just out.

The Ingersoll Dollar Watch
It Runs with the Sun!



The reputation of the **Ingersoll Dollar Watch** is firmly established as an accurate, reliable timepiece. Its splendid performances have gained the faith of the nation. "The test of time"—in both senses of the phrase—has demonstrated beyond a doubt that the watch is not a toy, but a practical timepiece, conventional in size, handsome in appearance and Guaranteed to Keep Accurate Time for One Year. For sale by 10,000 dealers, or sent postpaid in U. S. and Canada upon receipt of **$1.**
ROBT. H. INGERSOLL & BRO., Dept. 147, **67 Cortlandt St., New York, N. Y.**

American Sheet Steel Company
Battery Park Building
New York
Manufacturers of all varieties of
Iron and Steel Sheets
Black and Galvanized

W. Dewees Wood Company's
Planished Iron
Wellsville Polished Steel Sheets

If Your Eye Could See

the filth that passes through ordinary water faucets you would be alarmed and disgusted. These germs are the cause of most diseases. Pure water would prevent them and perfectly pure water can be produced only by using the widely celebrated
Berkefeld Filter,
which is constructed on the most scientific and hygienic principle. Easy to clean and care for. Rapid filtration. One gallon of pure water in 4 minutes.
Berkefeld Filter Co., 2 Cedar St., New York.

TUBULAR DRIVING LAMP.

IT is the only perfect one.
IT will not blow or jar out.
IT gives a clear, white light.
IT is like an engine headlight.
IT throws the light straight ahead from 200 to 300 ft.
IT burns kerosene,
Send for book (free).
R. E. DIETZ CO., 60 Laight Street, New York.
Mention this paper and get special discount.
ESTABLISHED 1840.

50 YEARS' EXPERIENCE
PATENTS
TRADE MARKS
DESIGNS
COPYRIGHTS &C.

Anyone sending a sketch and description may quickly ascertain our opinion free whether an invention is probably patentable. Communications strictly confidential. Handbook on Patents sent free. Oldest agency for securing patents.
Patents taken through Munn & Co. receive *special notice*, without charge, in the
Scientific American.
A handsomely illustrated weekly. Largest circulation of any scientific journal. Terms, $3 a year; four months, $1. Sold by all newsdealers.
MUNN & Co. 361 Broadway, **New York**
Branch Office, 625 F St., Washington, D. C.

THE HARRISON CONVEYOR—Electric Light and Power Station Equipment, Industrial Railways, Overhead Cable Systems, Coal and Ash Conveyors, etc., Eccentric Shaking Screens, Roller Screens, Elevators, Hoisting Engines, Clam Shell Buckets, Breaker Rolls, Picking Tables, Hows Standard Scales, Howe Gas and Gasoline Engines. For catalogue and prices, address the manufacturers.
BORDEN & SELLECK CO., - 48-50 LAKE STREET, CHICAGO, ILL.

NEW ILLUSTRATED CATALOGUE NOW READY. **Elevating-Conveying Machinery.** Send For Copy.
Address THE JEFFREY MFG. CO., COLUMBUS, OHIO. U. S. A.

GERE GASOLINE ENGINES
SIMPLEST BOAT ENGINES MADE
CABIN AND OPEN BOATS
ENGINE CASTINGS, BOAT FRAMES
GEO. M. GERE YACHT AND LAUNCH WKS.
GRAND RAPIDS, MICHIGAN.
NEW CAT FOR 4 STAMPS

SECTORLESS WIMSHURST MACHINE.—This article gives directions for making. 4 illustrations. SCIENTIFIC AMERICAN SUPPLEMENT **1131.** Price 10 cents. For sale by Munn & Co. and all newsdealers. Send for new catalogue.

THE LAMP OF LAMPS

For every outdoor purpose the new electric light,
CLOVER LEAF LAMP
is the best. Wind and water proof. Cannot blow out. Best for carriages, automobiles, yachts, boats, etc. A strong, safe and handsome lamp—easily convertible into a house lamp. Will give continuous light for fifty or sixty hours. No smoke, no grease, no smell. Price, with 3-cell battery, $15.
American Electrical Novelty & Mfg. Co.,
255 Centre Street, New York.
Write for 1900-1901 Catalogue of Electrical Novelties.

A DESIRABLE HOLIDAY GIFT.
DRAPER'S
Recording Thermometer
Standardized and Warranted.
Gives a correct and continous record in ink on a weekly chart.
☞ *Write for Particulars.*
THE DRAPER MFG. CO.,
152 Front Street, New York.

ACETYLENE APPARATUS
Acetylene number of the SCIENTIFIC AMERICAN SUPPLEMENT, describing, with full illustrations, the most recent, simple or home made and commercial apparatus for generating acetylene on the large and small scale. The gas as made for and used by the microscopist and student; its use in the magic lantern. The new French table lamp making its own acetylene. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **1057.** Price 10 cents prepaid by mail. For other numerous valuable articles on this subject we refer you to page 21 of our new 1897 Supplement Catalogue, sent free to any address. MUNN & Co., 361 Broadway, New York.

New System of Gas and Gasoline Engine Ignition.



FOR **AUTOMOBILES, LAUNCHES, GAS ENGINES, POWER,** ETC.
WILLIAM ROCHE,
Illustrated Descriptive Circular Free. Inventor and Sole Manufacturer New Standard Dry Battery.
42 VESEY STREET, NEW YORK CITY.

N. Y. CAMERA EXCHANGE.

50% Saved on all makes of Cameras
Headquarters for Buying, Selling and Exchanging Cameras or Lenses. Large assortment always on hand.
Developing, Printing, etc.
Photo supplies of every description at *lowest prices.*
☞ *Send 2c. stamp for bargain list.* Address
N. Y. CAMERA EXCHANGE, 114 Fulton St., NEW YORK

SPECIAL OFFER!
American $10 Typewriter!
We will give the first person answering this ad., from each town in the United States, a splendid opportunity to obtain the American Typewriter, the only standard low-priced typewriter on the market, on unusually attractive terms. Write promptly for catalogue and sample work, and see if our offer does not interest you.
American Typewriter Company, 267 B'way, New York.

Electrical Scientific Novelties.
Models of Locomotives, Railways, Dynamos, Motors, etc.

Safe, Practical, Durable.
THE CARLISLE & FINCH CO.,
233 East Clifton Avenue, Cincinnati, Ohio.

ONLY THE SUNART CAMERAS MEET ALL REQUIREMENTS
28 STYLES.
PRICE $5.00 TO $50.00
SEND FOR CATALOGUE TO
SUNART PHOTO CO. 5 AQUEDUCT STR. ROCHESTER, N.Y.

A. W. FABER
Manufactory Established 1761.
LEAD PENCILS, COLORED PENCILS, SLATE PENCILS, WRITING SLATES. STEEL PENS, GOLD PENS, INKS, PENCIL CASES IN SILVER AND IN GOLD, STATIONERS' RUBBER GOODS, RULERS. COLORS AND ARTISTS' MATERIALS
78 Reade Street. - - - New York. N. Y.
Paris Exposition, 1900. Grand Prize. Highest Award.

REVERSING STEAM TURBINE.—Parson's recently perfected turbine for boats. Illustrations showing details. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **1158.** Price 10 cents, by mail, from this office, and from all newsdealers.

PERFORATED METALS FOR MINING SCREENS,
COAL AND ORE SEPARATORS, REVOLVING AND SHAKING SCREENS,
JIGS & STAMP BATTERIES FOR ALL KINDS OF MILLING & MINING MACHINERY AND ALL OTHER USES.
HARRINGTON & KING PERFORATING CO. 229 W. UNION ST. CHICAGO.

We Tell You All About it in
THE BOOK OF THE NEW CENTURY



The finest catalogue ever issued is yours on request. If interested in typewriters, you ought to have it.
AMERICAN WRITING MACHINE CO.,
302 BROADWAY, NEW YORK.

The Typewriter Exchange

1½ Barclay St., NEW YORK
124 La Salle St., CHICAGO
38 Bromfield St., BOSTON
817 Wyandotte St., KANSAS CITY, MO.
209 North 9th St., ST. LOUIS, MO.
432 Diamond St., PITTSBURGH, PA.
3 West Baltimore St., BALTIMORE, MD.
536 California St., SAN FRANCISCO, CAL.
We will save you from 10 to 50% on Typewriters of all makes. *Send for Catalogue.*

The No. 4 YOST WRITING MACHINE

The distinctive features of the Yost Machine, permanent alignment, direct inking, beautiful work, strength, simplicity, and durability are shown in perfection in the No. 4 Model.
Yost Writing Machine Co.
NEW YORK CITY. LONDON, ENG.

NOW READY.
AN AMERICAN BOOK ON
Horseless Vehicles, Automobiles and Motor Cycles.
OPERATED BY
Steam, Hydro-Carbon, Electric and Pneumatic Motors.
By GARDNER D. HISCOX, M. E.
Author of "Gas, Gasolene and Oil Vapor Engines," and "Mechanical Movements, Devices and Appliances."
PRICE $3.00 POSTPAID.

This work is written on a broad basis, and comprises in its scope a full illustrated description with details of the progress and manufacturing advance of one of the most important innovations of the times, contributing to the pleasure and business convenience of mankind.
The make-up and management of Automobile Vehicles of all kinds is liberally treated, and in a way that will be appreciated by those who are reaching out for a better knowledge of the new era in locomotion.
The book is up to date and very fully illustrated with various types of Horseless Carriages, Automobiles and Motor Cycles, with details of the same.
Large 8vo. About 400 pages. Very Fully Illustrated.
☞ *Send for circular of contents.*
MUNN & CO. 361 Broadway, New York

Brass Band

Instruments, Drums Uniforms, & Supplies. Write for catalog, 445 illustrations, FREE; it gives information for musicians and new bands. **LYON & HEALY,**
38 Adams St., CHICAGO.

BILLIARD $100 TABLE.
4X8 — OR — 4½X9 ft.
COMPLETE OUTFIT REGULAR GOODS.
NO BABY STUFF.
HARD WOOD NATURAL FINISH.
OTHER STYLES UP TO $500.
B. A. STEVENS TOLEDO, OHIO, U.S.A.

That's where our education affects you.

What The International Correspondence Schools, Scranton, Pa., are doing :

FIRST
Teaching mechanics the theory of their work.

SECOND
Helping misplaced people to change their work.

THIRD
Enabling young people to support themselves while learning professions.

250,000 students and graduates in **Mechanical, Electrical, Steam, Civil and Mining Engineering; Architecture; Plumbing; Heating; Refrigeration; Pattern Drafting; Drawing and Designing; Chemistry; Telegraphy; Telephony; Stenography; Book-keeping; English Branches; Methods of Teaching.** When writing, state subject in which interested.

INTERNATIONAL CORRESPONDENCE SCHOOLS
Established 1891. Capital, $1,500,000
Box 942 Scranton, Pa.

SPECIAL OFFER
to 500 "Scientific American" Subscribers

Zon-o-phone

THE NEW DISCOVERY
that has elevated a Talking Machine to the Realm of Art.

Technically speaking, the ZON-O-PHONE is a Talking Machine; practically, it is something very different. It is in the delightful entertaining, satisfying quality of its results that the ZON-O-PHONE is entirely different from anything you have ever heard before.

For the first time, the **distinctly human quality** of both the speaking and the singing voice is faithfully retained. For the first time the colorature performances of the great sopranos, even to their faintest trills and most rapid runs, are recorded **with tone quality unimpaired** and reproduced in a manner to delight the most critical. For the first time, the sweet and elusive notes and chords of the Violin are successfully registered. For the first time, in the grand **ensemble** work of the orchestra and military band, the detail of the various instruments is preserved in tone effects of marvelous richness, depth and beauty. For the first time, also, extraneous noise is eliminated, even the scratch of the needle.

These superb results are largely due to the vast improvements we have been able to make in the records. By a secret process, recently discovered, we register thousands of minute sound vibrations which are entirely lost by all other methods. To illustrate this to the eye :—

This line represents a sound wave as recorded by the old and now abandoned Gram-o-phone process,

and this line the same sound wave as recorded by the new ZON-O-PHONE process showing the multiplicity of vibrations which have before escaped registration.

In other respects also, the ZON-O-PHONE is a vast improvement over all other Talking Machines, including the Gram-o-phone, which we have abandoned, including its name. In one word, the ZON-O-PHONE is the only ARTISTIC, and therefore the only entirely satisfactory Talking Machine. Its repertoire of Records covers everything available in the amusement world; and as a source of lasting, varied and delightful Home Entertainment, it is without a rival.

SPECIAL OFFER TO 500 SUBSCRIBERS OF THE "SCIENTIFIC AMERICAN."

If you are actually a subscriber to the "SCIENTIFIC AMERICAN," we will send you a ZON-O-PHONE outfit complete, including Zon-o-phone, Amplifying Horn, Sound Box and 200 Needles, with four superb Zon-o-phone Records, on payment of One Dollar as an evidence of good faith, provided you are one of the **first 500 subscribers** who answer this Advertisement. The ZON-O-PHONE outfit will be sent on these terms, subject to 24 hours examination. If you are pleased with it, as we are sure you will be, it may be bought outright for $20.00, or on installments, as may be agreed. If, after examining the ZON-O-PHONE, you do not desire to keep it, we will refund the $1.00 on receipt of the ZON-O-PHONE outfit.

NATIONAL GRAM-O-PHONE CORPORATION, 874 Broadway, New York.

THE ORIGINAL AND GENUINE ::

Rubber Goods. Perfectly imitate linen. Are durable and keep white. They go to all parts of the Globe. Write for Catalog. We want Agents everywhere. M'f'd only by
Windsor Collar & Cuff Co., Windsor, Conn.

THE MODERN ICE YACHT.—BY GEO. W. POLK. A new and valuable paper, containing full, practical directions and specifications for the construction of the fastest and best kinds of Ice Yachts of the latest, most approved forms. Illustrated with engravings drawn to scale, showing the form, position, and arrangement of all the parts. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 624. Price 10 cents. To be had at this office and of all newsdealers.

AGENTS WANTED TO SELL
THE STANDARD GAS LAMP.
A wonderful invention. 1-6 the expense of kerosene, or 6 times the light. Perfectly safe. 41 different styles. Retail from $4 up. All brass. Country people can now have light brighter than electricity and cheaper than kerosene. Can furnish thousands of testimonials from people using them for months. Agents coining money. Write for exclusive territory. STANDARD GAS LAMP CO., 118-120 Michigan Street, Chicago, Ill.

FREE! WHOLESALE BOOK CATALOG
Edition for 1900-1901
Now ready. Costs 6 cents Postage to Mail. 416 pages, 6 by 9 inches, advertising 15,000 Books, Bibles, Periodicals, etc., etc., at Wholesale Prices. All books carried in stock. Best catalog ever printed and sent free of charge.
THE BOOK SUPPLY COMPANY, 266-8 Wabash Ave., Chicago.

ICE MACHINES, Corliss Engines, Brewers' and Bottlers' Machinery. THE VILTER MFG. CO., 899 Clinton Street, Milwaukee, Wis.

TYPE WHEELS. MODELS & EXPERIMENTAL WORK. SMALL MACHINERY NOVELTIES & ETC. NEW YORK STENCIL WORKS 100 NASSAU ST. N.Y.

MODELS & EXPERIMENTAL WORK. Inventions developed. Special Machinery. E. V. BAILLARD, Fox Bldg., Franklin Square, New York.

D'AMOUR & LITTLEDALE MACHINE CO.
130 WORTH ST. NEW YORK.
PATTERN AND MODEL MAKERS.

1-2 H. P. GAS ENGINE CASTINGS
Materials and Blue Prints. Write for Catalogue 9.
PARSELL & WEED, 129-131 W. 31st Street, New York.

MODELS & GEARS CATALOGUE FREE. UNION MODEL WORKS 193 CLARK CHICAGO.

AMERICAN MANUFACTURERS
desirous of being represented in France and Europe, address for particulars, JULES FLEISCH, 76 Rue Mozart, Paris, France. Best references furnished.

WANTED.—An experienced Cost Keeper. One accustomed to both iron and woodworking preferred. Apply, with references, by letter only, The New Domestic S. M. Co., 98 Warren St., Newark, N. J.

326 FIRST PREMIUMS SEND FOR FREE CATALOGUE. Prairie State Incubator Co., Homer City, Pa.

FOR SALE.—Machine Shop, brass and iron foundry not large, but well equipped. Present owners not active nor conversant with the business. A thoroughly capable man who would know what and how to manufacture, with some capital, can buy this plant on very easy terms. Address
WATERTOWN MFG. CO., Watertown, Wis.

FOR SALE.
Adjustable bicycle saddle post. Something new. Great advantage. Simple and practical device. Big demand. Address **BOX 153,** Station C, Los Angeles, Cal.

FRICTION CLUTCHES
Simplest and Surest. Write for Catalogue.
EMPIRE MOTOR WORKS,
900 Washington Street, Buffalo, N. Y.

RED CEDAR SILOS.
AIR AND WATER TIGHT. ANY DIAMETER, ANY DEPTH.
WILLIAMS MFG CO. KALAMAZOO MICH.

Magneto for Gas or Gasoline Engine Igniters
No batteries used. Self-lubricating bearings. Dust and moisture proof. Brushes self-adjusting. Material and workmanship the BEST. GUARANTEED FOR ONE YEAR. Send for circular and price list.
GIDDINGS & STEVENS, Rockford, Ill.

U. S GOVERNMENT SOLD 10,000

Spanish Mauser Rifles & Carbines
also 5,000,000 Ball Cartridges in clips. **We bought them all.** Before exporting them, we offer a limited number at retail.
F. BANNERMAN, 579 Broadway New York.
Catalog on request. Dealer in Military Goods and War Relics

MOVING PICTURE MACHINES AND FILMS.
MAGIC LANTERNS WANTED AND FOR SALE OR EXCHANGE
HARBACH & CO. 809 Filbert St. Phila. Pa.

D. L. HOLDEN
14 South Broad St. Philadelphia Pa.
SOLE MANUFACTURER
REGEALED ICE MACHINES
SEE FIRST PAGE SCIENTIFIC AMERICAN SEPT. 2. 1899.

ELECTRICAL ENGINEERING TAUGHT BY MAIL.
Write for our Free Illustrated Book.
"CAN I BECOME AN ELECTRICAL ENGINEER?"

We teach Electrical Engineering, Electric Lighting, Electric Railways, Mechanical Engineering, Steam Engineering, Mechanical Drawing, at your home by mail. Institute indorsed by Thos. A. Edison and others.
ELECTRICAL ENGINEER INSTITUTE,
Dept. A, 240-242 W. 23d St., New York.

IMPORTED ALL J.V.S. LAVA SCHWARZ PERFECTION

Acetylene Gas Burners.
Schwarz Perfection Lava Burner.
Highest awards in all Acetylene Expositions. Made of one piece of *lava*. Are faultless and *every one tested and guaranteed.* ☞ *Send for Price List.*
NO Blowing. Smoking. Carbonization. Perfect Alignment.
Sole Agents for the U. S. and Canada.
M. KIRCHBERGER & CO.
50 Warren Street, New York.

The Pipe of the Century.
...THE... **"MALLINCKRODT" PATENT**
NICOTINE ABSORBENT AND VENTILATED SMOKING PIPE IS THE ONLY PIPE FIT FOR A GENTLEMAN'S USE.

You may appreciate the exquisite flavor and taste of a good smoking tobacco, but you can never have that enjoyment with a dirty, foul-smelling pipe, thoroughly saturated with poisonous nicotine juices, so bitter and disgusting to the taste. This is effectually remedied in the "Mallinckrodt" where the juices are completely absorbed before reaching the mouth, and assuring a cool, clean and healthy smoke. Money refunded if not satisfactory. Pipes from 30 to 50 cents each, according to size and finish. Over 100,000 sold in 1899 alone.
Send for illustrated circular "S. A." with prices.
THE HARVEY & WATTS CO.,
275 Canal Street. N. Y. Station E. Philadelphia.

CROSBY'S GLOVES
Factory to Family by mail post-paid.
Our great $3.00 black gauntlet fur gloves; ladies' Mocha kid gloves **in any color** $1.25; men's Mocha and Reindeer gloves unlined and silk lined $1.50 to $2.00; many other kinds of gloves and mittens 60 cents and upwards, all in illustrated booklet "Glove Pointers." **Natural Black Galloway, Calfskin,** and other fur coats; Galloway whole hide robes, Taxidermy and Head Mounting in booklet "Moth-Proof." Do you want hides or skins tanned for rugs or robes? get our "Custom Tan Folder." We also buy raw furs.
THE CROSBY FRISIAN FUR COMPANY,
116 Mill Street, Rochester, N. Y.

JUST PUBLISHED

THE Progress of Invention IN THE Nineteenth Century

By EDWARD W. BYRN, A. M.

LARGE OCTAVO. 480 PAGES. 300 ILLUSTRATIONS. PRICE $3.00 BY MAIL POSTPAID TO ANY COUNTRY IN THE WORLD. HALF RED MOROCCO, GILT TOP, $4.00.

Readers of the SCIENTIFIC AMERICAN are aware to what extent it has devoted itself for more than half a century to chronicling the great inventions and discoveries of the present century; and to worthily commemorate the completion of the nineteenth century its publishers are about to bring out a scholarly and interesting volume which will present in concrete form the great scientific and engineering achievements of the century. The chapters give a most comprehensive and coherent account of the progress which distinguishes this as the "golden age of invention," resulting in industrial and commercial development which is without precedent. A chronological calendar of the leading inventions is one of the important features of the book, enabling the reader to refer at a glance to the inventions and discoveries of any particular year. The book is printed with large type, on fine paper, and is elaborately illustrated by 300 engravings and is attractively bound.

Every reader of the SCIENTIFIC AMERICAN should possess a copy of this unique and timely publication.

The following is a brief Table of Contents. Chapter I—The Perspective View. II—Chronology of Leading Inventions of the Nineteenth Century. III—The Electric Telegraph. IV—The Atlantic Cable. V—The Dynamo and Its Applications. VI The Electric Motor. VII—The Electric Light. VIII—The Telephone. IX—Electricity, Miscellaneous. X—The Steam Engine. XI—The Steam Railway. XII—Steam Navigation. XIII—Printing. XIV—The Typewriter. XV—The Sewing Machine. XVI—The Reaper. XVII—Vulcanized Rubber. XVIII—Chemistry. XIX—Food and Drink. XX—Medicine, Surgery and Sanitation. XXI—The Bicycle and Automobile. XXII—The Phonograph. XXIII—Optics. XXIV—Photography. XXV—The Roentgen or X-Rays. XXVI—Gas Lighting. XXVII—Civil Engineering. XXVIII—Woodworking. XXIX—Metal Working. XXX—Fire Arms and Explosives. XXXI—Textiles. XXXII—Ice Machines. XXXIII—Liquid Air. XXXIV—Minor Inventions. XXXV—Epilogue.

A full Table of Contents, with samples of illustrations, is now ready and will be sent free to any address.

MUNN & CO., PUBLISHERS,
SCIENTIFIC AMERICAN OFFICE, 361 BROADWAY, NEW YORK.

VELOCITY OF ICE BOATS.—A COLlection of interesting letters to the editor of the SCIENTIFIC AMERICAN on the question of the speed of Ice Boats, demonstrating how and why it is that these craft sail faster than the wind which propels them. Illustrated with 10 explanatory diagrams. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 214. Price 10 cents. To be had at this office and from all newsdealers.

$3 a Day Sure Send us your address and we will show you how to make $3 a day absolutely sure; we furnish the work and teach you free, you work in the locality where you live. Send us your address and we will explain the business fully, remember we guarantee a clear profit of $3 for every day's work, absolutely sure. Write at once.
ROYAL MANUFACTURING CO., Box 354, Detroit, Mich.

ELECTRICAL MACHINERY BARGAINS
ARC LAMPS. ALL KINDS AND SIZES OF DYNAMOS ENGINES MOTORS ETC
CORRESPOND WITH US TO BUY OR SELL
THOMPSON SON & CO. 105 LIBERTY ST. N. Y.



INCUBATORS THE CYPHERS.
One Style Only, OUR BEST.
Warranted to last Ten Years and to out-hatch any other incubator—bar none; THIS OR YOUR MONEY BACK. Circular and price list FREE. Poultry Manual and Catalogue No. 134, 15c.
CYPHERS INCUBATOR CO.,
Boston, Mass. Wayland, N. Y. Chicago, Ill.

LIFE PRODUCERS
SUCCESSFUL INCUBATORS.
LIFE PRESERVERS
SUCCESSFUL BROODERS.
All about them in our 154 page catalogue. Mailed for 6 cents in stamps.
DES MOINES INCUBATOR CO., Box 75 Des Moines, Ia.

200 Egg Incubator For $12.00.
The simplest, most perfect incubator made in the world. This is a new one at a remarkably low price. It is an enlargement of the famous
WOODEN HEN
and made as thoroughly good as any incubator on the market. It will hatch every fertile egg put in it, and stand up to regular usage as well as the most costly. Write for free catalogue.

GEO. H. STAHL, Quincy, Ill.

FOR MEN OF BRAINS

Cortez Cigars

—MADE AT KEY WEST—

These Cigars are manufactured under the most favorable climatic conditions and from the mildest blends of Havana tobacco. If we had to pay the imported cigar tax our brands would cost double the money. Send for booklet and particulars.

CORTEZ CIGAR CO., KEY WEST.

THOROUGH INSPECTIONS

HARTFORD STEAM BOILER INSPECTION AND INSURANCE CO. HARTFORD, CONN.

AND INSURANCE AGAINST LOSS OR DAMAGE TO PROPERTY AND LOSS OF LIFE AND INJURY TO PERSONS CAUSED BY

STEAM BOILER EXPLOSIONS

J. M. ALLEN, President — W. B. FRANKLIN, Vice President
J. B. PIERCE, Secretary — F. B. ALLEN, 2d Vice President
L. B. BRAINERD, Treas. — L. F. MIDDLEBROOK, Asst Secy

NO CHEAPER TRAVELING



Price $1,200.

can be experienced than when riding in a

WINTON MOTOR CARRIAGE

It costs half a cent a mile to operate. Speed can be regulated at will. Easy of control, absolutely safe. Simple, but perfect in every detail of its construction, elegant in design, handsome and durable in finish. All parts interchangeable but none liable to get out of order.

THE WINTON MOTOR CARRIAGE CO., Cleveland, Ohio.

AUTOMOBILE PATENTS EXPLOITATION COMPANY.

UNDERTAKES:—The manufacture of Automobiles and Motor-Cycles. The examination of Automobile patents. To enlist capital for the development of inventions.

FURNISHES:—Specialists to make thorough examinations of patents. Experts to test motors and automobiles. Opportunities to inventors to present properly their propositions to concerns willing to consider and to undertake the same.

PURCHASES:—All meritorious patents, licenses and inventions relating to motor-cycles, motors, gears, automobiles and their parts.

F. B. HYDE, Secretary. 27 William St., New York.

A Racing Machine

FORTY MILES AN HOUR



if you want it, but we do not recommend our customers to buy racers unless they are going to make racing a business. Our standard speed is 18 miles per hour on country roads. We furnish powerful double cylinder, variable speed gasoline engines with our carriages; ample power and strong construction; elegant design and fine workmanship.

Prospective buyers send for descriptive matter. **Immediate delivery. No agents.**

THE HAYNES-APPERSON CO., - KOKOMO, INDIANA.

CHARTER ENGINE

USED ANY PLACE BY ANY ONE FOR ANY PURPOSE

FUEL—Gasoline, Gas, Distillate

Stationaries, Portables, Engines and Pumps, Hoisters

☞ State Your Power Needs

CHARTER GAS ENGINE CO., Box 148, STERLING, ILL.

NOT FOR FARMERS ONLY.

THE

Country Gentleman

The ONLY Agricultural NEWSpaper,

AND ADMITTEDLY THE

LEADING AGRICULTURAL JOURNAL OF THE WORLD.

Every department written by specialists, the highest authorities in their respective lines.

Gives the agricultural NEWS with a degree of fullness and completeness not even attempted by others.

INDISPENSABLE TO

ALL COUNTRY RESIDENTS

Single Subscriptions, $2.
Two Subscriptions, $3.50.
Four Subscriptions, $6.

SPECIAL INDUCEMENTS TO RAISERS OF LARGER CLUBS.

Four Months' Trial Trip 50 Cents.

It will pay anybody interested in any way in country life to send for sample copies.

LUTHER TUCKER & SON,
ALBANY, N. Y.

WALTHAM WATCHES

It is not alone the value of the jewels that makes a first-class watch---it is the brains that have planned its construction. It is mechanical skill and knowledge that have made Waltham Watches the best in the world.

"The Perfected American Watch", an illustrated book of interesting information about watches, will be sent free upon request.

American Waltham Watch Company,
Waltham, Mass.



1 Candle Power Lamps.
8 Lamps in Series on 100 to 120 volts.
4 Lamps in Series on 50 to 60 volts.

CHRISTMAS LIGHTING

EDISON MINIATURE LAMPS

for Christmas Trees.

No Danger, Smoke or Smell. Lamps either rented or sold. Full directions furnished, enabling anyone to readily wire and put up the lamps.

Can be used only in houses having electric lights.

Address

GENERAL ELECTRIC COMPANY,
HARRISON, N. J.

Do You Know That Your Razor Has Teeth

Its edge is not a straight, but a serrated line and the finer the teeth the better the razor. Ordinary shaving lathers injure these teeth by invisible corrosion. This is what puts a razor out of order, compelling frequent stropping and honing.

ELECTRO SHAVING LATHER

is a new and scientific improvement in a shaving outfit. It preserves and hardens the delicate teeth of the razor, makes it cut easier, soothes the skin, is easy to make and delightful to use. Send for free folder giving particulars.

F. G. FOWLER & CO., Bridgeport, Conn., U.S.A.



GARDNER GRINDER FOR FLAT SURFACES ACCURATE & RAPID FOR UP-TO-DATE SHOPS
C. H. BESLY & CO. CHICAGO ILL. U.S.A.

ACETYLENE

DO YOU KNOW that the most light, least trouble, greatest comfort can be secured by using good burners. The best burner is D. M. STEWARD'S WONDER. Write, inclosing 25 cents, for sample.

STATE LINE TALC CO., Chattanooga, Tenn., U. S. A.

MORROW COASTER BRAKE.

FITS ANY CYCLE. 100,000 IN USE
ADDS PLEASURE AND SAFETY—ALL DEALERS SELL THEM.
RIDE 50 MILES—PEDAL ONLY 35. ECLIPSE MANUFACTURING Co., BOX X, ELMIRA, N.Y.
SEND FOR BOOKLET.

INVENTORS' MERCANTILE BUREAU 320 Broadway, New York, with correspondents in all foreign countries. Have facilities for the Manufacture and Introduction of Patent Novelties. Send Model and Plans and we will make you an offer.

GRAMOPHONES!



THE

United States Gramophone Co.,

Stewart Bldg., Washington, D. C.,

owns the **Letters Patent** for the **GRAMOPHONE** and its **Indestructible Record Discs.** These patents have never been attacked, nor have Gramophones and Records made under them ever been declared infringements, except through judgments **confessed** by a former agent of the Gramophone; such judgments have no legal value. The Gramophone patents cover all Talking Machines in which the **record groove propels the stylus,** and in which **hard-pressed record discs** are used.

SUITS HAVE BEEN ENTERED AGAINST the parties offering the **Zon-o-phone (a bold copy of the Gramophone).**

Dealers and users are **WARNED** against buying them, or they make themselves liable for heavy damages.

United States Gramophone Company,

Canadian Parties Address:
E. BERLINER, 2315 St. Catherine Street, MONTREAL.

E. BERLINER, Pres.

ASBESTOS FIRE-FELT COVERINGS

PURE ASBESTOS, REPLETE WITH AIR CELLS, STRONG, LIGHT, FLEXIBLE. ABSOLUTELY FIRE PROOF. PERFECT NON-CONDUCTORS. EASILY APPLIED.

MADE IN SECTIONS THREE FEET LONG, FIT STANDARD PIPE ½ INCH TO 16 INCHES.

H. W. JOHNS MFG CO.
NEW YORK · CHICAGO · PHILADELPHIA · BOSTON
MAKERS OF
ASBESTOS MATERIALS, LIQUID PAINTS & STAINS
ROOFING MATERIALS, ELECTRICAL MATERIALS

The New England Watch Co.

ARTISTIC SPECIALTIES for the Season are shown In Our Blue Book for Ladies' In Our Red Book for Men's **Watches.**

Either or both sent on application.

37 Maiden Lane, New York, N. Y.
149 State Street, Chicago, Ill.
Spreckels Building, San Francisco, Cal.

LAUGHLIN FOUNTAIN PEN.

THE BEST AT ANY PRICE

A Holiday Suggestion—A gift of never ending usefulness and a constant pleasant reminder of the giver. **Your Choice** of these popular styles, superior to the

$3.00 STYLES

of other makes, for only

$1.00

Try it a Week. If not suited, we buy it back. Finest quality hard rubber holder, 14k. Diamond Point Gold Pen, any desired flexibility in fine, medium or stub, and the only perfect ink feed. By mail, postpaid on receipt of $1.00, (registration 8c. extra.)

Ask your dealer to show you **this** pen. If he has not or won't get it for you (do not let him substitute an imitation, on which he can make more profit). send his name and your order to us, and receive, **free of charge,** one of our Safety Pocket Pen Holders.

Remember, there **is no "just as good" as the Laughlin. Insist on** it; take no chances.

(Illustrations two-thirds size.)

LAUGHLIN MFG. CO.,
310 Laughlin Block,
DETROIT, MICH.

"LIGHT OF ASIA" LAMP

The Smallest Portable Electric Light.

Weight, 5¼ oz.
⅝ in. diam.
8 ins. long.

Unlike all other portable lights, the batteries of the "Light of Asia" Lamp **do not deteriorate** unless used. For a good light for short intervals, this lamp is unexcelled. The "**Light of Asia**" Lamp is made with a view to beauty, and is mounted in an aluminum shell covered with fine leather. Price **$3.00,** postpaid.

Every One Guaranteed.

ELECTRIC CONTRACT CO.
61 ELM STREET, NEW YORK.

MINERAL PRODUCT OF THE UNITED States in 1895-1896.—A valuable table, accompanied by statistics. SCIENTIFIC AMERICAN SUPPLEMENT 1119. Price 10 cents. For sale by Munn & Co. and all newsdealers. Send for 1897 catalogue.

EDISON RECORDS



FOR GOOD MUSIC

Buy Edison Records. Dealers everywhere have them. Ask for the RED HAND kind.

GENUINE EDISON PHONOGRAPHS
From $10. to $100. Catalogues everywhere, all dealers.

None genuine without this Thomas A Edison Trade Mark.

Nat'l Phonograph Co., 135 Fifth Av., New York

Scales All varieties at lowest prices. Best Railroad Track and Wagon or Stock Scales made. Also 1000 useful articles, including Safes, Sewing Machines, Bicycles, Tools, etc. Save Money. Lists Free. CHICAGO SCALE CO., Chicago, Ill.

JESSOP'S STEEL AWARDED Grand Prix at Paris, 1900, for Excellence in Quality and Workmanship.
NEW YORK OFFICE, 91 JOHN STREET.